

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	4367.50 123.70
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	4300.70 121.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	4262.45 120.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	4233.90 119.90
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	3262.95 92.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	3205.50 90.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	3171.50 89.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	3148.05 89.15
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3670.55 103.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3605.00 102.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3565.50 101.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3538.15 100.20
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3146.40 89.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	3060.85 86.70
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	3010.40 85.25
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2975.30 84.25

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1616.25 45.75	4848.90 137.30
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	4715.25 133.55
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	4648.45 131.65
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	4610.20 130.55
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	4582.90 129.80
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1164.60 33.00	3637.40 103.00
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	3523.75 99.80
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	3466.35 98.15
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	3433.55 97.25
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	3408.90 96.55
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1141.35 32.30	4121.30 116.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3987.70 112.95
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3922.10 111.10
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3882.65 109.95
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3855.30 109.20
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3578.30 101.35
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3407.20 96.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	3321.65
		Cu.ft.	25.85	94.05
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3272.45
		Cu.ft.	25.85	92.70
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3236.10
		Cu.ft.	25.85	91.65
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1797.35	4529.10
		Cu.ft.	50.90	128.25
ii)	Cement sand mortar 1 : 4	Cu.m.	1797.35	4462.30
		Cu.ft.	50.90	126.35
iii)	Cement sand mortar 1 : 5	Cu.m.	1797.35	4424.05
		Cu.ft.	50.90	125.30
iv)	Cement sand mortar 1 : 6	Cu.m.	1797.35	4396.70
		Cu.ft.	50.90	124.50
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1345.70	3429.40
		Cu.ft.	38.10	97.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1345.70	3371.95
		Cu.ft.	38.10	95.50
iii)	Cement sand mortar 1 : 5	Cu.m.	1345.70	3339.15
		Cu.ft.	38.10	94.55
iv)	Cement sand mortar 1 : 6	Cu.m.	1345.70	3315.75
		Cu.ft.	38.10	93.90
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1311.00	3824.35
		Cu.ft.	37.15	108.30
ii)	Cement sand mortar 1 : 4	Cu.m.	1311.00	3757.55
		Cu.ft.	37.15	106.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1311.00	3719.30
		Cu.ft.	37.15	105.35
iv)	Cement sand mortar 1 : 6	Cu.m.	1311.00	3691.95
		Cu.ft.	37.15	104.55

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-4	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3130.50 88.65
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	3046.20 86.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2995.80 84.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2960.65 83.85
	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1797.35 50.90	5008.00 141.85
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1797.35 50.90	4875.65 138.10
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1797.35 50.90	4808.80 136.20
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1797.35 50.90	4770.55 135.10
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1797.35 50.90	4742.00 134.30
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1345.70 38.10	3802.65 107.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1345.70 38.10	3689.00 104.45
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1345.70 38.10	3631.55 102.85
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1345.70 38.10	3598.75 101.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1345.70 38.10	3575.35 101.25
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3869.00 109.55
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3736.60 105.80
iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	3671.05 103.95	



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3631.55
		Cu.ft.	25.85	102.85
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3604.25
		Cu.ft.	25.85	102.05
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	912.20	3561.20
		Cu.ft.	25.85	100.85
ii)	Cement sand mortar 1 : 3	Cu.m.	912.20	3391.35
		Cu.ft.	25.85	96.05
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	3305.80
		Cu.ft.	25.85	93.60
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3255.40
		Cu.ft.	25.85	92.20
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3220.25
		Cu.ft.	25.85	91.20
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	273.85	273.85
		Cu.ft.	7.75	7.75
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	217.75	217.75
		Cu.ft.	6.15	6.15
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80