

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	4217.65 119.45
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	4150.85 117.55
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	4112.60 116.45
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	4084.05 115.65
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	3150.90 89.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	3093.45 87.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	3060.65 86.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	3037.25 86.00
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3535.90 100.15
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3469.10 98.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3430.80 97.15
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3402.25 96.35
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3039.35 86.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2953.80 83.65
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2903.40 82.25
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2868.25 81.25

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1616.25 45.75	4708.05 133.35
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	4574.40 129.55
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	4508.85 127.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	4469.35 126.55
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	4442.00 125.80
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1164.60 33.00	3533.35 100.05
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	3418.45 96.80
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	3362.25 95.20
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	3328.25 94.25
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	3304.80 93.60
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1141.35 32.30	3993.60 113.10
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3861.20 109.35
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3794.40 107.45
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3754.95 106.35
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3727.60 105.55
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3478.00 98.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3306.90 93.65

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	3221.40
		Cu.ft.	25.85	91.25
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3170.95
		Cu.ft.	25.85	89.80
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3135.85
		Cu.ft.	25.85	88.80
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1797.35	4380.45
		Cu.ft.	50.90	124.05
ii)	Cement sand mortar 1 : 4	Cu.m.	1797.35	4313.65
		Cu.ft.	50.90	122.15
iii)	Cement sand mortar 1 : 5	Cu.m.	1797.35	4275.40
		Cu.ft.	50.90	121.10
iv)	Cement sand mortar 1 : 6	Cu.m.	1797.35	4246.85
		Cu.ft.	50.90	120.25
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1345.70	3318.55
		Cu.ft.	38.10	94.00
ii)	Cement sand mortar 1 : 4	Cu.m.	1345.70	3261.15
		Cu.ft.	38.10	92.35
iii)	Cement sand mortar 1 : 5	Cu.m.	1345.70	3228.35
		Cu.ft.	38.10	91.45
iv)	Cement sand mortar 1 : 6	Cu.m.	1345.70	3204.90
		Cu.ft.	38.10	90.75
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1311.00	3689.70
		Cu.ft.	37.15	104.50
ii)	Cement sand mortar 1 : 4	Cu.m.	1311.00	3622.85
		Cu.ft.	37.15	102.60
iii)	Cement sand mortar 1 : 5	Cu.m.	1311.00	3584.60
		Cu.ft.	37.15	101.50
iv)	Cement sand mortar 1 : 6	Cu.m.	1311.00	3557.30
		Cu.ft.	37.15	100.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-4	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3024.70 85.65
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2939.15 83.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2888.75 81.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2853.60 80.80
	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1797.35 50.90	4868.40 137.90
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1797.35 50.90	4734.75 134.10
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1797.35 50.90	4669.20 132.25
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1797.35 50.90	4630.90 131.15
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1797.35 50.90	4602.40 130.35
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1345.70 38.10	3698.55 104.75
ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1345.70 38.10	3584.90 101.55	
iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1345.70 38.10	3528.70 99.95	
iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1345.70 38.10	3494.70 98.95	
v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1345.70 38.10	3471.25 98.30	
c) 8" (200 mm) thick hollow block masonry				
i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3742.55 106.00	
ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3610.15 102.25	
iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	3544.55 100.40	

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3505.05
		Cu.ft.	25.85	99.25
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3477.75
		Cu.ft.	25.85	98.50
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	912.20	3460.95
		Cu.ft.	25.85	98.00
ii)	Cement sand mortar 1 : 3	Cu.m.	912.20	3291.05
		Cu.ft.	25.85	93.20
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	3205.50
		Cu.ft.	25.85	90.80
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3156.35
		Cu.ft.	25.85	89.40
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3119.95
		Cu.ft.	25.85	88.35
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	273.85	273.85
		Cu.ft.	7.75	7.75
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	217.75	217.75
		Cu.ft.	6.15	6.15
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80