

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	3781.60 107.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	3714.80 105.20
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	3676.55 104.10
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	3648.00 103.30
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	2822.60 79.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	2766.40 78.35
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	2732.35 77.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	2708.95 76.70
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3137.45 88.85
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3070.65 86.95
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3032.35 85.90
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3003.80 85.05
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2707.25 76.65
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2621.70 74.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2571.30 72.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2536.15 71.85

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1616.25 45.75	4296.25 121.65
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	4162.65 117.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	4097.05 116.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	4057.55 114.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	4030.25 114.15
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1164.60 33.00	3223.25 91.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	3109.60 88.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	3052.15 86.45
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	3019.35 85.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	2994.70 84.80
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1141.35 32.30	3618.50 102.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3484.85 98.70
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3418.05 96.80
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3379.80 95.70
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3352.45 94.95
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3164.10 89.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2993.00 84.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	2907.50
		Cu.ft.	25.85	82.35
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	2858.30
		Cu.ft.	25.85	80.95
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	2821.95
		Cu.ft.	25.85	79.90
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1797.35	3945.65
		Cu.ft.	50.90	111.75
ii)	Cement sand mortar 1 : 4	Cu.m.	1797.35	3878.80
		Cu.ft.	50.90	109.85
iii)	Cement sand mortar 1 : 5	Cu.m.	1797.35	3840.55
		Cu.ft.	50.90	108.75
iv)	Cement sand mortar 1 : 6	Cu.m.	1797.35	3813.25
		Cu.ft.	50.90	108.00
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1345.70	2991.50
		Cu.ft.	38.10	84.70
ii)	Cement sand mortar 1 : 4	Cu.m.	1345.70	2935.30
		Cu.ft.	38.10	83.15
iii)	Cement sand mortar 1 : 5	Cu.m.	1345.70	2902.50
		Cu.ft.	38.10	82.20
iv)	Cement sand mortar 1 : 6	Cu.m.	1345.70	2877.85
		Cu.ft.	38.10	81.50
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1311.00	3293.65
		Cu.ft.	37.15	93.30
ii)	Cement sand mortar 1 : 4	Cu.m.	1311.00	3226.85
		Cu.ft.	37.15	91.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1311.00	3188.60
		Cu.ft.	37.15	90.30
iv)	Cement sand mortar 1 : 6	Cu.m.	1311.00	3161.30
		Cu.ft.	37.15	89.55

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
<b>d)</b>	<b>12" (300 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2693.85 76.30
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2608.30 73.85
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2559.10 72.50
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2522.75 71.45
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
<b>a)</b>	<b>4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1797.35 50.90	4457.80 126.25
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1797.35 50.90	4325.45 122.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1797.35 50.90	4259.85 120.65
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1797.35 50.90	4220.35 119.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1797.35 50.90	4193.05 118.75
<b>b)</b>	<b>6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1345.70 38.10	3390.90 96.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1345.70 38.10	3277.25 92.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1345.70 38.10	3219.80 91.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1345.70 38.10	3187.05 90.25
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1345.70 38.10	3163.60 89.60
<b>c)</b>	<b>8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3368.60 95.40
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3236.20 91.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	3170.65 89.80

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	3131.15
		Cu.ft.	25.85	88.70
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	3103.85
		Cu.ft.	25.85	87.90
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	912.20	3149.45
		Cu.ft.	25.85	89.20
ii)	Cement sand mortar 1 : 3	Cu.m.	912.20	2978.40
		Cu.ft.	25.85	84.35
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	2892.85
		Cu.ft.	25.85	81.95
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	2843.65
		Cu.ft.	25.85	80.55
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	2808.50
		Cu.ft.	25.85	79.55
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	273.85	273.85
		Cu.ft.	7.75	7.75
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	217.75	217.75
		Cu.ft.	6.15	6.15
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80