

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4282.55 121.30
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4210.75 119.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4168.30 118.05
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4138.85 117.20
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3401.60 96.35
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3339.80 94.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3304.45 93.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3279.15 92.85
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3604.90 102.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3532.95 100.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3490.50 98.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3461.05 98.00
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3121.40 88.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3029.30 85.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2975.05 84.25
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2937.15 83.20


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1799.65 50.95	4830.55 136.80
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4686.70 132.75
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4614.75 130.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4572.30 129.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4542.85 128.65
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1498.20 42.45	3827.35 108.40
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3704.90 104.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3643.10 103.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3607.75 102.15
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3581.25 101.40
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1315.45 37.25	4116.00 116.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3972.15 112.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3900.20 110.45
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3858.95 109.30
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3828.30 108.40
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3609.00 102.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3423.50 96.95



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3331.35
		Cu.ft.	30.20	94.35
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3278.35
		Cu.ft.	30.20	92.85
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3239.25
		Cu.ft.	30.20	91.75
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2054.15	4518.90
		Cu.ft.	58.15	128.00
ii)	Cement sand mortar 1 : 4	Cu.m.	2054.15	4446.95
		Cu.ft.	58.15	125.95
iii)	Cement sand mortar 1 : 5	Cu.m.	2054.15	4405.70
		Cu.ft.	58.15	124.75
iv)	Cement sand mortar 1 : 6	Cu.m.	2054.15	4376.25
		Cu.ft.	58.15	123.95
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1752.70	3642.70
		Cu.ft.	49.65	103.15
ii)	Cement sand mortar 1 : 4	Cu.m.	1752.70	3580.85
		Cu.ft.	49.65	101.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1752.70	3545.50
		Cu.ft.	49.65	100.40
iv)	Cement sand mortar 1 : 6	Cu.m.	1752.70	3520.25
		Cu.ft.	49.65	99.70
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1552.75	3826.35
		Cu.ft.	43.95	108.35
ii)	Cement sand mortar 1 : 4	Cu.m.	1552.75	3754.45
		Cu.ft.	43.95	106.35
iii)	Cement sand mortar 1 : 5	Cu.m.	1552.75	3713.20
		Cu.ft.	43.95	105.15
iv)	Cement sand mortar 1 : 6	Cu.m.	1552.75	3683.70
		Cu.ft.	43.95	104.30

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3105.55 87.95
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3013.40 85.35
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2960.40 83.85
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2922.50 82.75
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2054.15 58.15	5063.10 143.40
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2054.15 58.15	4920.45 139.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2054.15 58.15	4848.50 137.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2054.15 58.15	4807.25 136.15
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2054.15 58.15	4777.80 135.30
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1752.70 49.65	4066.00 115.15
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1752.70 49.65	3943.55 111.70
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1752.70 49.65	3882.95 109.95
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1752.70 49.65	3846.35 108.95
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1752.70 49.65	3821.10 108.20
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3844.35 108.85
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3701.75 104.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3629.80 102.80



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3588.55
		Cu.ft.	30.20	101.65
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3559.10
		Cu.ft.	30.20	100.80
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1066.95	3590.70
		Cu.ft.	30.20	101.70
ii)	Cement sand mortar 1 : 3	Cu.m.	1066.95	3407.65
		Cu.ft.	30.20	96.50
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3315.50
		Cu.ft.	30.20	93.90
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3261.25
		Cu.ft.	30.20	92.35
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3223.35
		Cu.ft.	30.20	91.30
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	373.25	373.25
		Cu.ft.	10.55	10.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	303.60	303.60
		Cu.ft.	8.60	8.60
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80