


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5077.15 143.80
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	4989.25 141.30
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	4939.05 139.90
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4901.95 138.85
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3953.40 111.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3878.40 109.85
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3834.15 108.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3803.40 107.70
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4292.55 121.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4205.25 119.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4153.80 117.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4117.95 116.60
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3756.95 106.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3643.85 103.20
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3578.05 101.35
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3531.95 100.05

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5634.90 159.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5570.50 157.75
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5483.20 155.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5433.00 153.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5395.90 152.80
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4378.60 124.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4323.25 122.45
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4248.25 120.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4205.20 119.10
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4174.50 118.20
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	4806.20 136.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4741.80 134.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4654.50 131.80
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4604.30 130.40
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4567.20 129.35
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4209.20 119.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4126.80 116.85



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	4014.90
		Cu.ft.	33.55	113.70
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3949.10
		Cu.ft.	33.55	111.85
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3901.80
		Cu.ft.	33.55	110.50
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	5321.45
		Cu.ft.	64.65	150.70
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	5234.15
		Cu.ft.	64.65	148.25
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	5183.95
		Cu.ft.	64.65	146.80
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	5148.10
		Cu.ft.	64.65	145.80
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	4203.20
		Cu.ft.	52.85	119.05
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	4129.45
		Cu.ft.	52.85	116.95
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	4085.15
		Cu.ft.	52.85	115.70
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	4054.40
		Cu.ft.	52.85	114.80
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4524.70
		Cu.ft.	48.55	128.15
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4437.40
		Cu.ft.	48.55	125.65
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4387.20
		Cu.ft.	48.55	124.25
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	4350.10
		Cu.ft.	48.55	123.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3737.45 105.85
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3625.55 102.70
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3560.95 100.85
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3514.85 99.55
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	5877.35 166.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	5813.00 164.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	5725.70 162.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	5675.45 160.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	5639.60 159.70
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4627.20 131.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4571.85 129.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4496.85 127.35
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4453.80 126.15
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4423.05 125.25
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4500.70 127.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4436.30 125.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	4349.00 123.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4298.80
		Cu.ft.	33.55	121.75
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4262.95
		Cu.ft.	33.55	120.75
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	4188.50
		Cu.ft.	33.55	118.60
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	4106.05
		Cu.ft.	33.55	116.30
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3994.15
		Cu.ft.	33.55	113.10
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3929.60
		Cu.ft.	33.55	111.30
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3883.50
		Cu.ft.	33.55	110.00
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80