


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	4893.95 138.60
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	4804.25 136.05
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	4752.85 134.60
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4714.90 133.55
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3812.40 107.95
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3735.65 105.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3691.60 104.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3658.90 103.60
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4123.05 116.75
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4033.70 114.25
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	3981.10 112.75
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	3944.35 111.70
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3603.20 102.05
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3487.45 98.75
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3420.15 96.85
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3372.95 95.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5514.00 156.15
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5412.45 153.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5321.90 150.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5270.45 149.25
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5232.55 148.20
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4288.45 121.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4201.25 119.00
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4124.50 116.80
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4079.20 115.55
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4047.70 114.65
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	4696.70 133.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4595.10 130.15
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4505.75 127.60
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4453.15 126.10
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4415.20 125.05
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4122.25 116.75
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3990.80 113.00

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3876.30
		Cu.ft.	33.55	109.80
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3808.95
		Cu.ft.	33.55	107.85
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3761.75
		Cu.ft.	33.55	106.55
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	5139.75
		Cu.ft.	64.65	145.55
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	5050.40
		Cu.ft.	64.65	143.05
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	4999.00
		Cu.ft.	64.65	141.55
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	4961.05
		Cu.ft.	64.65	140.50
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	4063.45
		Cu.ft.	52.85	115.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	3986.70
		Cu.ft.	52.85	112.90
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	3942.60
		Cu.ft.	52.85	111.65
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	3911.15
		Cu.ft.	52.85	110.75
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4355.25
		Cu.ft.	48.55	123.35
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4267.10
		Cu.ft.	48.55	120.85
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4214.50
		Cu.ft.	48.55	119.35
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	4177.75
		Cu.ft.	48.55	118.30

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3584.90 101.55
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3470.40 98.30
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3404.30 96.40
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3355.85 95.05
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	5756.50 163.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	5654.95 160.15
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	5565.55 157.60
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	5514.15 156.15
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	5476.20 155.10
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4537.05 128.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4449.80 126.00
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4373.05 123.85
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4329.00 122.60
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4297.50 121.70
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4391.20 124.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4289.60 121.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	4200.25 118.95



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4148.85
		Cu.ft.	33.55	117.50
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4110.90
		Cu.ft.	33.55	116.40
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	4101.55
		Cu.ft.	33.55	116.15
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	3971.30
		Cu.ft.	33.55	112.45
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3856.75
		Cu.ft.	33.55	109.25
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3790.65
		Cu.ft.	33.55	107.35
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3742.25
		Cu.ft.	33.55	106.00
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80