

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	4918.50 139.30
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	4835.85 136.95
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	4786.80 135.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4752.65 134.60
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3831.10 108.50
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3760.85 106.50
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3718.60 105.30
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3689.35 104.50
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4145.55 117.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4062.35 115.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4014.50 113.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	3979.15 112.70
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3624.05 102.65
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3517.45 99.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3454.70 97.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3409.60 96.55


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5449.05 154.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5389.40 152.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5306.20 150.25
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5258.40 148.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5223.00 147.90
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4235.50 119.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4185.40 118.55
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4113.90 116.50
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4071.70 115.30
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4042.45 114.50
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	4634.10 131.25
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4574.45 129.55
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4491.25 127.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4443.45 125.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4408.05 124.85
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4053.45 114.80
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3977.15 112.65



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3870.50
		Cu.ft.	33.55	109.60
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3807.80
		Cu.ft.	33.55	107.85
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3763.90
		Cu.ft.	33.55	106.60
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	5163.95
		Cu.ft.	64.65	146.25
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	5080.75
		Cu.ft.	64.65	143.90
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	5032.90
		Cu.ft.	64.65	142.55
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	4998.75
		Cu.ft.	64.65	141.55
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	4082.10
		Cu.ft.	52.85	115.60
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	4011.85
		Cu.ft.	52.85	113.60
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	3969.65
		Cu.ft.	52.85	112.40
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	3940.35
		Cu.ft.	52.85	111.60
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4378.95
		Cu.ft.	48.55	124.00
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4295.75
		Cu.ft.	48.55	121.65
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4246.70
		Cu.ft.	48.55	120.25
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	4212.55
		Cu.ft.	48.55	119.30

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3605.75 102.10
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3499.15 99.10
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3437.65 97.35
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3393.70 96.10
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	5691.50 161.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	5633.10 159.55
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	5549.90 157.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	5502.05 155.80
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	5466.70 154.80
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4484.05 127.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4434.00 125.55
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4362.50 123.55
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4321.50 122.40
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4292.20 121.55
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4328.60 122.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4270.20 120.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	4187.00 118.60



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4139.15
		Cu.ft.	33.55	117.20
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4103.80
		Cu.ft.	33.55	116.20
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	4033.95
		Cu.ft.	33.55	114.25
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	3957.65
		Cu.ft.	33.55	112.10
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3851.00
		Cu.ft.	33.55	109.05
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3789.50
		Cu.ft.	33.55	107.30
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3744.35
		Cu.ft.	33.55	106.05
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80