


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5487.00 155.40
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5397.10 152.85
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5345.70 151.40
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5307.75 150.30
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4269.50 120.90
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4192.75 118.75
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4147.45 117.45
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4115.95 116.55
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4673.35 132.35
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4584.00 129.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4531.35 128.35
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4493.40 127.25
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4106.45 116.30
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3990.70 113.00
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3924.60 111.15
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3876.15 109.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5978.30 169.30
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5976.60 169.25
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5887.25 166.75
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5835.85 165.25
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5797.90 164.20
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4637.95 131.35
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4636.50 131.30
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4559.75 129.15
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4515.65 127.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4483.00 126.95
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	5120.85 145.05
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	5119.15 145.00
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	5029.80 142.45
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4977.15 140.95
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4940.45 139.90
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4475.65 126.75
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4473.45 126.70

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	4358.90
		Cu.ft.	33.55	123.45
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4291.60
		Cu.ft.	33.55	121.55
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4243.15
		Cu.ft.	33.55	120.15
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	5728.90
		Cu.ft.	64.65	162.25
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	5640.80
		Cu.ft.	64.65	159.75
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	5588.15
		Cu.ft.	64.65	158.25
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	5551.45
		Cu.ft.	64.65	157.20
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	4518.05
		Cu.ft.	52.85	127.95
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	4441.30
		Cu.ft.	52.85	125.80
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	4397.25
		Cu.ft.	52.85	124.55
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	4364.55
		Cu.ft.	52.85	123.60
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4903.10
		Cu.ft.	48.55	138.85
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4813.70
		Cu.ft.	48.55	136.35
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4762.30
		Cu.ft.	48.55	134.85
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	4724.35
		Cu.ft.	48.55	133.80

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4085.70 115.70
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3971.15 112.45
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3905.05 110.60
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3856.65 109.20
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	6218.35 176.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	6216.65 176.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	6128.50 173.55
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	6075.85 172.05
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	6039.15 171.05
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4885.30 138.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4883.85 138.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4807.10 136.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4763.05 134.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4730.35 133.95
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4812.90 136.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4811.20 136.25
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	4721.85 133.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4670.45
		Cu.ft.	33.55	132.25
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4633.75
		Cu.ft.	33.55	131.25
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	4453.65
		Cu.ft.	33.55	126.15
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	4451.50
		Cu.ft.	33.55	126.05
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	4336.95
		Cu.ft.	33.55	122.80
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4270.85
		Cu.ft.	33.55	120.95
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4222.40
		Cu.ft.	33.55	119.60
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80