

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6173.25 174.85
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6075.95 172.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6018.55 170.45
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5977.20 169.30
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4803.75 136.05
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4719.95 133.65
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4671.80 132.30
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4636.20 131.30
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5266.85 149.15
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5169.30 146.40
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5111.90 144.75
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5070.55 143.60
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4580.75 129.75
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4455.65 126.20
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4382.20 124.10
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4329.35 122.60




Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6798.90 192.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6722.00 190.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6624.45 187.60
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6568.25 186.00
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6526.90 184.85
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5281.80 149.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5215.75 147.70
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	5131.95 145.35
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	5083.80 144.00
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	5048.15 142.95
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5843.90 165.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5767.05 163.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5669.50 160.55
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5612.05 158.95
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5570.70 157.75
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5092.45 144.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4992.70 141.40

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4867.65
		Cu.ft.	36.95	137.85
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4794.15
		Cu.ft.	36.95	135.75
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4741.35
		Cu.ft.	36.95	134.30
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6462.65
		Cu.ft.	71.55	183.05
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6366.30
		Cu.ft.	71.55	180.30
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6308.90
		Cu.ft.	71.55	178.65
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6268.75
		Cu.ft.	71.55	177.55
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	5100.20
		Cu.ft.	59.05	144.45
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	5017.65
		Cu.ft.	59.05	142.10
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4968.25
		Cu.ft.	59.05	140.70
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4933.85
		Cu.ft.	59.05	139.75
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5536.10
		Cu.ft.	53.90	156.80
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5438.55
		Cu.ft.	53.90	154.00
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5382.35
		Cu.ft.	53.90	152.45
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5341.00
		Cu.ft.	53.90	151.25

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4558.75 129.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4433.70 125.55
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4360.20 123.50
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4308.60 122.00
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	7086.80 200.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	7009.90 198.50
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6912.35 195.75
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6856.20 194.15
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6814.80 193.00
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5575.85 157.90
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5511.00 156.05
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5427.20 153.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5379.05 152.35
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5343.40 151.35
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5505.80 155.95
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5428.90 153.75
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5331.35 151.00



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5275.20
		Cu.ft.	36.95	149.40
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5233.80
		Cu.ft.	36.95	148.20
				
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	5066.80
		Cu.ft.	36.95	143.50
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4968.30
		Cu.ft.	36.95	140.70
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4843.25
		Cu.ft.	36.95	137.15
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4771.00
		Cu.ft.	36.95	135.10
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4718.15
		Cu.ft.	36.95	133.60
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80