

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5860.15 165.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5767.75 163.35
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5713.30 161.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5675.30 160.75
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4564.00 129.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4484.60 127.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4439.00 125.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4405.20 124.75
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	4977.10 140.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4884.65 138.35
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4831.45 136.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4792.20 135.70
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4321.90 122.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4203.45 119.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4133.80 117.05
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4083.75 115.65




Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6473.80 183.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6384.95 180.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6292.50 178.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6239.30 176.70
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6200.10 175.60
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5034.50 142.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4958.20 140.40
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4878.80 138.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4833.20 136.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4799.40 135.90
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5544.50 157.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5455.65 154.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5363.25 151.90
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5308.80 150.35
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5270.80 149.25
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4831.25 136.80
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4716.15 133.55



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4597.65
		Cu.ft.	36.95	130.20
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4528.00
		Cu.ft.	36.95	128.25
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4477.95
		Cu.ft.	36.95	126.80
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6151.75
		Cu.ft.	71.55	174.20
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6059.30
		Cu.ft.	71.55	171.60
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6006.10
		Cu.ft.	71.55	170.10
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	5966.90
		Cu.ft.	71.55	169.00
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4861.65
		Cu.ft.	59.05	137.70
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4783.50
		Cu.ft.	59.05	135.45
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4736.65
		Cu.ft.	59.05	134.15
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4704.10
		Cu.ft.	59.05	133.20
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5248.75
		Cu.ft.	53.90	148.65
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5156.35
		Cu.ft.	53.90	146.05
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5101.90
		Cu.ft.	53.90	144.50
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5063.90
		Cu.ft.	53.90	143.40

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4301.20 121.80
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4182.70 118.45
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4113.05 116.50
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4064.20 115.10
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6762.95 191.55
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6674.10 189.00
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6581.65 186.40
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6528.45 184.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6490.45 183.80
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5329.75 150.95
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5254.65 148.80
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5175.25 146.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5129.65 145.25
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5095.85 144.30
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5207.65 147.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5120.00 145.00
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5027.60 142.40

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4973.15
		Cu.ft.	36.95	140.85
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4935.15
		Cu.ft.	36.95	139.75
				
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4806.85
		Cu.ft.	36.95	136.15
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4692.95
		Cu.ft.	36.95	132.90
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4574.45
		Cu.ft.	36.95	129.55
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4506.05
		Cu.ft.	36.95	127.60
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4456.00
		Cu.ft.	36.95	126.20
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80