

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5993.40 169.75
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5899.20 167.05
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5845.40 165.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5805.75 164.40
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4666.95 132.15
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4586.65 129.90
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4539.30 128.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4506.40 127.60
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5100.80 144.45
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5007.35 141.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4952.30 140.25
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4913.85 139.15
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4433.05 125.55
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4312.05 122.10
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4241.65 120.15
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4192.25 118.75


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6593.70 186.75
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6520.00 184.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6426.55 182.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6371.50 180.45
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6333.10 179.35
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5124.30 145.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5060.90 143.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4980.65 141.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4934.50 139.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4900.35 138.80
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5653.10 160.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5580.60 158.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5485.90 155.35
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5432.10 153.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5392.45 152.70
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4922.70 139.40
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4827.05 136.70



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4707.25
		Cu.ft.	36.95	133.30
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4636.85
		Cu.ft.	36.95	131.30
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4587.45
		Cu.ft.	36.95	129.90
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6284.25
		Cu.ft.	71.55	177.95
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6190.80
		Cu.ft.	71.55	175.35
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6136.95
		Cu.ft.	71.55	173.80
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6097.30
		Cu.ft.	71.55	172.70
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4963.40
		Cu.ft.	59.05	140.55
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4884.35
		Cu.ft.	59.05	138.35
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4837.00
		Cu.ft.	59.05	137.00
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4804.05
		Cu.ft.	59.05	136.05
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5371.25
		Cu.ft.	53.90	152.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5277.80
		Cu.ft.	53.90	149.45
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5222.75
		Cu.ft.	53.90	147.90
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5184.35
		Cu.ft.	53.90	146.80

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4411.10 124.90
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4291.30 121.55
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4220.90 119.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4171.50 118.15
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6881.65 194.90
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6807.90 192.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6714.45 190.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6660.65 188.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6622.20 187.55
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5419.50 153.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5356.15 151.70
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5277.10 149.45
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5229.75 148.10
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5196.80 147.20
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5316.20 150.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5243.70 148.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5150.25 145.85



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5095.20
		Cu.ft.	36.95	144.30
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5056.80
		Cu.ft.	36.95	143.20
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4898.30
		Cu.ft.	36.95	138.70
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4803.85
		Cu.ft.	36.95	136.05
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4684.05
		Cu.ft.	36.95	132.65
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4613.65
		Cu.ft.	36.95	130.65
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4564.25
		Cu.ft.	36.95	129.25
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80