


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2167.55 61.40	6647.65 188.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2167.55 61.40	6549.45 185.50
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2167.55 61.40	6493.25 183.90
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2167.55 61.40	6451.90 182.70
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1729.65 49.00	5164.50 146.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1729.65 49.00	5080.70 143.90
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1729.65 49.00	5031.30 142.50
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1729.65 49.00	4996.90 141.50
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1578.90 44.70	5713.35 161.80
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1578.90 44.70	5615.80 159.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1578.90 44.70	5558.40 157.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1578.90 44.70	5518.25 156.30
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1278.25 36.20	4997.10 141.50
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1278.25 36.20	4870.80 137.95
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1278.25 36.20	4797.35 135.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1278.25 36.20	4744.50 134.35



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2167.55 61.40	7152.05 202.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2167.55 61.40	7173.15 203.15
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2167.55 61.40	7075.60 200.40
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2167.55 61.40	7018.20 198.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2167.55 61.40	6978.05 197.60
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1729.65 49.00	5539.50 156.90
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1729.65 49.00	5557.55 157.40
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1729.65 49.00	5473.80 155.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1729.65 49.00	5425.60 153.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1729.65 49.00	5390.00 152.65
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1578.90 44.70	6170.95 174.75
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1578.90 44.70	6192.05 175.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1578.90 44.70	6094.50 172.60
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1578.90 44.70	6037.10 170.95
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1578.90 44.70	5996.95 169.85
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1278.25 36.20	5363.05 151.90
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1278.25 36.20	5390.20 152.65

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1278.25	5265.10
		Cu.ft.	36.20	149.10
iv)	Cement sand mortar 1 : 5	Cu.m.	1278.25	5191.65
		Cu.ft.	36.20	147.05
v)	Cement sand mortar 1 : 6	Cu.m.	1278.25	5138.85
		Cu.ft.	36.20	145.55
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2473.35	6923.45
		Cu.ft.	70.05	196.10
ii)	Cement sand mortar 1 : 4	Cu.m.	2473.35	6825.90
		Cu.ft.	70.05	193.30
iii)	Cement sand mortar 1 : 5	Cu.m.	2473.35	6769.70
		Cu.ft.	70.05	191.70
iv)	Cement sand mortar 1 : 6	Cu.m.	2473.35	6729.60
		Cu.ft.	70.05	190.60
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2035.40	5447.05
		Cu.ft.	57.65	154.25
ii)	Cement sand mortar 1 : 4	Cu.m.	2035.40	5364.50
		Cu.ft.	57.65	151.95
iii)	Cement sand mortar 1 : 5	Cu.m.	2035.40	5315.10
		Cu.ft.	57.65	150.55
iv)	Cement sand mortar 1 : 6	Cu.m.	2035.40	5280.70
		Cu.ft.	57.65	149.55
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1861.80	5970.60
		Cu.ft.	52.75	169.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1861.80	5874.30
		Cu.ft.	52.75	166.35
iii)	Cement sand mortar 1 : 5	Cu.m.	1861.80	5816.85
		Cu.ft.	52.75	164.75
iv)	Cement sand mortar 1 : 6	Cu.m.	1861.80	5776.75
		Cu.ft.	52.75	163.60

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1278.25 36.20	4971.50 140.80
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1278.25 36.20	4846.40 137.25
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1278.25 36.20	4774.15 135.20
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1278.25 36.20	4721.35 133.70
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2473.35 70.05	7424.85 210.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2473.35 70.05	7445.95 210.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2473.35 70.05	7349.65 208.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2473.35 70.05	7292.20 206.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2473.35 70.05	7252.10 205.40
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2035.40 57.65	5820.85 164.85
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2035.40 57.65	5838.95 165.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2035.40 57.65	5756.35 163.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2035.40 57.65	5706.95 161.60
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2035.40 57.65	5672.55 160.65
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1278.25 36.20	5836.15 165.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1278.25 36.20	5858.45 165.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1278.25 36.20	5760.90 163.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1278.25	5703.50
		Cu.ft.	36.20	161.55
v)	Cement sand mortar 1 : 6	Cu.m.	1278.25	5663.35
		Cu.ft.	36.20	160.40
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1278.25	5336.20
		Cu.ft.	36.20	151.10
ii)	Cement sand mortar 1 : 3	Cu.m.	1278.25	5364.60
		Cu.ft.	36.20	151.95
iii)	Cement sand mortar 1 : 4	Cu.m.	1278.25	5239.50
		Cu.ft.	36.20	148.40
iv)	Cement sand mortar 1 : 5	Cu.m.	1278.25	5166.05
		Cu.ft.	36.20	146.30
v)	Cement sand mortar 1 : 6	Cu.m.	1278.25	5114.45
		Cu.ft.	36.20	144.85
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	443.25	443.25
		Cu.ft.	12.55	12.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	359.95	359.95
		Cu.ft.	10.20	10.20
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80