


| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-1 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2209.50 62.55 | 6125.00 173.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2209.50 62.55 | 6029.25 170.75 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2209.50 62.55 | 5973.00 169.15 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2209.50 62.55 | 5933.75 168.05 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1767.75 50.05 | 4767.65 135.00 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1767.75 50.05 | 4685.60 132.70 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1767.75 50.05 | 4637.25 131.35 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1767.75 50.05 | 4603.55 130.40 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1611.30 45.65 | 5221.95 147.90 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1611.30 45.65 | 5126.45 145.20 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1611.30 45.65 | 5070.20 143.60 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1611.30 45.65 | 5030.95 142.50 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 4542.70 128.65 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 4420.25 125.20 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1304.90 36.95 | 4348.30 123.15 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1304.90 36.95 | 4296.60 121.70 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-2 | Same as item 10-1 but in 1:2:4 concrete hollow block masonry. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2209.50 62.55 | 6735.55 190.75 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2209.50 62.55 | 6661.40 188.65 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2209.50 62.55 | 6565.85 185.95 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2209.50 62.55 | 6509.65 184.35 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2209.50 62.55 | 6469.15 183.20 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1767.75 50.05 | 5232.30 148.20 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1767.75 50.05 | 5169.80 146.40 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1767.75 50.05 | 5087.75 144.10 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1767.75 50.05 | 5039.40 142.70 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1767.75 50.05 | 5005.75 141.75 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1611.30 45.65 | 5784.35 163.80 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1611.30 45.65 | 5710.20 161.70 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1611.30 45.65 | 5614.70 159.00 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1611.30 45.65 | 5558.50 157.40 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1611.30 45.65 | 5519.20 156.30 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1304.90 36.95 | 5039.85 142.75 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 4944.85 140.05 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1304.90 | 4821.20 |
| | | Cu.ft. | 36.95 | 136.55 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 4750.50 |
| | | Cu.ft. | 36.95 | 134.55 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 4698.75 |
| | | Cu.ft. | 36.95 | 133.05 |
| 10-3 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2526.70 | 6415.10 |
| | | Cu.ft. | 71.55 | 181.70 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2526.70 | 6319.60 |
| | | Cu.ft. | 71.55 | 178.95 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2526.70 | 6264.60 |
| | | Cu.ft. | 71.55 | 177.40 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2526.70 | 6225.30 |
| | | Cu.ft. | 71.55 | 176.30 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2084.95 | 5064.10 |
| | | Cu.ft. | 59.05 | 143.40 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2084.95 | 4982.05 |
| | | Cu.ft. | 59.05 | 141.10 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2084.95 | 4934.90 |
| | | Cu.ft. | 59.05 | 139.75 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2084.95 | 4901.25 |
| | | Cu.ft. | 59.05 | 138.80 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1903.75 | 5492.40 |
| | | Cu.ft. | 53.90 | 155.55 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1903.75 | 5396.90 |
| | | Cu.ft. | 53.90 | 152.85 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1903.75 | 5340.70 |
| | | Cu.ft. | 53.90 | 151.25 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1903.75 | 5301.40 |
| | | Cu.ft. | 53.90 | 150.15 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 4520.75 128.05 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 4398.30 124.55 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1304.90 36.95 | 4326.35 122.50 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1304.90 36.95 | 4275.85 121.10 |
| 10-4 | Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry. | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2526.70 71.55 | 7022.25 198.85 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2526.70 71.55 | 6948.10 196.75 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2526.70 71.55 | 6853.80 194.10 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2526.70 71.55 | 6797.60 192.50 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2526.70 71.55 | 6758.30 191.40 |
| b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2084.95 59.05 | 5527.55 156.55 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2084.95 59.05 | 5463.80 154.75 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2084.95 59.05 | 5383.00 152.45 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2084.95 59.05 | 5334.65 151.10 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2084.95 59.05 | 5300.95 150.15 |
| c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1304.90 36.95 | 5446.25 154.25 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 5373.30 152.20 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 5277.80 149.45 |



| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|--------|------------|-----------|
| | | | Labour | Composite |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 5221.60 |
| | | Cu.ft. | 36.95 | 147.90 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 5182.30 |
| | | Cu.ft. | 36.95 | 146.75 |
|  | | | | |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1304.90 | 5015.45 |
| | | Cu.ft. | 36.95 | 142.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1304.90 | 4920.45 |
| | | Cu.ft. | 36.95 | 139.35 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1304.90 | 4798.00 |
| | | Cu.ft. | 36.95 | 135.90 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 4726.10 |
| | | Cu.ft. | 36.95 | 133.85 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 4675.60 |
| | | Cu.ft. | 36.95 | 132.40 |
| 10-5 | Extra for hollow block masonry in first floor superstructure. | Cu.m. | 454.45 | 454.45 |
| | | Cu.ft. | 12.85 | 12.85 |
| 10-6 | Extra for hollow block masonry in every additional floor above first floor. | Cu.m. | 371.20 | 371.20 |
| | | Cu.ft. | 10.50 | 10.50 |
| 10-7 | Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 83.55 | 98.15 |
| | | Cu.ft. | 2.35 | 2.80 |