


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5966.35 168.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5872.55 166.30
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5817.55 164.75
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5779.10 163.65
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4645.75 131.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4565.50 129.30
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4519.35 128.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4485.20 127.00
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5075.35 143.75
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4981.85 141.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4928.05 139.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4888.40 138.45
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4411.95 124.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4292.15 121.55
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4221.75 119.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4172.35 118.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6569.75 186.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6494.90 183.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6401.45 181.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6346.45 179.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6306.80 178.60
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5106.45 144.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5042.10 142.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4961.85 140.50
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4915.75 139.20
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4881.55 138.25
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5631.35 159.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5556.55 157.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5463.10 154.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5409.30 153.20
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5369.65 152.05
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4904.20 138.90
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4808.35 136.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4688.50
		Cu.ft.	36.95	132.80
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4618.15
		Cu.ft.	36.95	130.80
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4567.50
		Cu.ft.	36.95	129.35
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6257.60
		Cu.ft.	71.55	177.20
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6164.15
		Cu.ft.	71.55	174.55
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6110.35
		Cu.ft.	71.55	173.05
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6070.70
		Cu.ft.	71.55	171.95
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4943.45
		Cu.ft.	59.05	140.00
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4863.15
		Cu.ft.	59.05	137.75
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4817.05
		Cu.ft.	59.05	136.40
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4784.10
		Cu.ft.	59.05	135.50
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5345.80
		Cu.ft.	53.90	151.40
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5253.55
		Cu.ft.	53.90	148.80
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5198.55
		Cu.ft.	53.90	147.25
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5160.10
		Cu.ft.	53.90	146.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4391.25 124.35
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4271.45 120.95
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4201.05 119.00
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4151.60 117.60
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6857.65 194.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6782.85 192.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6689.40 189.45
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6635.55 187.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6597.15 186.85
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5401.70 153.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5337.35 151.15
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5258.30 148.90
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5210.95 147.60
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5178.05 146.65
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5294.50 149.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5219.65 147.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5127.40 145.20



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5072.40
		Cu.ft.	36.95	143.65
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5033.95
		Cu.ft.	36.95	142.55
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4881.00
		Cu.ft.	36.95	138.25
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4785.15
		Cu.ft.	36.95	135.50
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4665.35
		Cu.ft.	36.95	132.15
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4594.95
		Cu.ft.	36.95	130.15
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4545.55
		Cu.ft.	36.95	128.75
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80