

Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
13-1	a) Providing and laying roof insulation comprising single layer of first class burnt brick tile 9"x 4.5"x 1.5" laid with 1:6 cement sand mortar and grouted with 1:3 cement sand mortar laid over 4inches (100mm) thick earth and 1inch (25mm) thick gobi leaping over two coats of hot bitumen @ 34 lbs. per 100 Sq.ft.(1.65 Kg/Sq.m) sand blended covered with polythene sheet 300 gauge provided over single layer of tiles 12"x6"x1.25" laid in 1:6 cement sand mortar including 1:2 cement sand pointing underside of tiles including curing	Sq.m.	677.85	1700.25
		Sq.ft.	63.00	158.00
	b) Providing and laying first class burnt brick tile roofing laid in 1 : 6 cement sand mortar including 1 : 2 cement sand pointing underside of tiles including curing for Tee iron/girder roof (Cost of Tee iron/ girder not included)	Sq.m.	131.05	826.60
		Sq.ft.	12.20	76.80
c)	Extra if PCC tiles are used in place of first class burnt bricks in item 13-1(b) above	Sq.m.	45.85	289.30
		Sq.ft.	4.25	26.90
13-2	a) Providing and laying second class brick tile roofing comprising 4 inches (100mm) thick earth and 1 inch (25 mm) thick mud plaster with gobi leaping over 1/2 inch (13mm) thick cement plaster 1:6 with 34 lbs./100 Sq.ft.(1.65 Kg./Sq.m.) hot bitumen coating sand blended in one coat, provided over one layer of tiles 12" x 6"x 2" laid in 1:6 cement sand mortar including 1:2 cement sand pointing underside of tiles including curing	Sq.m.	513.85	1345.95
		Sq.ft.	47.75	125.10
b)	Providing and laying second class brick tile roofing comprising 4 inches (100mm) thick earth and 1 inch (25 mm) thick mud plaster with gobi leaping provided over one layer of tiles 12"x 6"x 2" laid in 1:6 cement sand mortar including 1:2 cement sand pointing underside of tiles including curing	Sq.m.	420.90	922.50
		Sq.ft.	39.10	85.75
13-3	Covering mud roof with coaltar 37 lbs./100 S.ft.(1.8 Kg /Sq.m) and fine sand.	Sq.m.	5.40	192.30
		Sq.ft.	0.50	17.85
13-4	a) Filling spaces in between: Wooden battens over beams filled with deodar wood pieces (spacers)	Sq.m.	69.30	128.90
		Sq.ft.	6.45	12.00
b)	R.C.C. battens over beams filled with cement concrete blocks 1 : 3 : 6	Sq.m.	105.65	140.75
		Sq.ft.	9.80	13.10
c)	Spaces filled with bricks in 1 : 3 cement sand	Sq.m.	8.55	111.80
		Sq.ft.	0.80	10.40
13-5	Providing and laying roof insulation comprising single layer of first class burnt brick tile 9"x 4.5"x 1.5" laid with 1:6 cement sand mortar and grouted with 1:3 cement sand mortar laid over 4inches (100mm) thick earth and 1inch (25mm) thick mud plaster without bhoosa over two coats of hot bitumen @ 34 lbs. per 100 Sq.ft.(1.65 Kg/Sq.m) sand blended covered with polythene sheet 300 gauge including curing etc. complete in all respect.	Sq.m.	229.85	1079.10
		Sq.ft.	21.35	100.30
13-6	a) Providing and filling earth over roof including watering, ramming, mud plastering with gobi leaping 3 inches (75mm) thick earth filling and mud plastering 1 inch (25mm) nominal thickness	Sq.m.	67.85	235.75
		Sq.ft.	6.30	21.90
b)	4 inches (100mm) thick earth filling and 1 inch (25 mm) thick mud plastering	Sq.m.	82.05	281.80
		Sq.ft.	7.65	26.20

Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
13-7	3.25 mm nominal thick gobar leaping on roof or floors.	Sq.m. Sq.ft.	14.05 1.30	16.15 1.50
13-8	Providing and fixing corrugated G.I. sheets with G.I. hooks, bolts, nuts, limpets and bitumen washers including cutting to required sizes and overlaps but without valleys and ridges (excluding cost of frame work) in ground floor			
a)	18 S.W.G. (1.41 mm) thick sheets roofing	Sq.m. Sq.ft.	85.60 7.95	2321.90 215.80
b)	20 S.W.G. (1.31 mm) thick sheets roofing	Sq.m. Sq.ft.	85.60 7.95	1762.20 163.75
c)	22 S.W.G. (1.21mm) thick sheets roofing	Sq.m. Sq.ft.	85.60 7.95	1408.15 130.85
d)	24 S.W.G. (1.06 mm) thick sheets roofing	Sq.m. Sq.ft.	85.60 7.95	1166.55 108.40
e)	26 S.W.G. (0.97 mm) thick sheets roofing	Sq.m. Sq.ft.	85.60 7.95	1038.80 96.55
13-9	Providing khassi parnalas in cement sand mortar 1 : 2, 12inches (300mm) outside width finished smooth with a floating coat of neat cement	R.M. R.ft.	254.75 77.65	350.60 106.85
13-10	Providing Khurras on roof 24" x 24" x 2" (600mm x 600mm x 50mm) size	Each	301.60	462.40
13-11	Providing bottom khurras of brick masonry in cement sand mortar 1:6, size 48"x24"x 1.5" (1250mmx 600mmx 38mm) over 3inches (75mm) thick cement concrete 1:4:8	Each	301.60	1282.80
13-12	Providing and laying plain galvanized iron sheet 22 SWG (1.21 mm) rain water down pipe including cost of clamps and fixing in position			
a)	4 inches (100 mm) diameter down pipe	R.M. R.ft.	187.40 57.10	336.90 102.70
b)	5 inches (125 mm) diameter down pipe	R.M. R.ft.	187.40 57.10	740.75 225.80
13-13	Providing and fixing plain galvanized iron sheet flashing 22 SWG (1.21mm)	Sq.m. Sq.ft.	737.85 68.55	2159.75 200.70
13-14	Providing and fixing in position cast iron rain water down pipe including painting and clamps but excluding heads and shoes			
a)	4 inches (100 mm) diameter C.I. down pipe	R.M. R.ft.	196.00 59.75	338.50 103.20
b)	3 inches (75 mm) diameter C.I. down pipe	R.M. R.ft.	196.00 59.75	215.10 65.55
13-15	Providing and fixing in position cast iron rain water down pipe head including cost of clamps, holdfasts, nuts, bolts and painting.			
a)	4 inches (100 mm) diameter C.I. head	Each	23.75	232.10
b)	3 inches (75 mm) diameter C.I. head	Each	23.75	198.75
13-16	Providing and fixing cast iron rain water pipe shoe, bend and offset including cost of clamps, holdfasts, bolts, nuts and painting			
a)	4 inches (100 mm) dia. shoe or bend or offset	Each	36.00	261.90

Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite



Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
b)	3 inches (80 mm) dia. shoe or bend or offset	Each	36.00	206.00
13-17	Providing and fixing plain 22 SWG (1.21 mm) G.I. sheet spout size 30"x6" (750mm x 150mm) including painting	Each	187.40	345.60
13-18	Providing and fixing plain G.I. sheets with G.I. bolts, nuts, limpets and bitumen washers including cutting to required sizes and overlaps but excluding cost of frame work in ground floor			
a)	18 SWG (1.41 mm.) thick sheet roofing	Sq.m. Sq.ft.	85.60 7.95	4241.75 394.20
b)	20 SWG (1.31 mm.) thick sheet roofing	Sq.m. Sq.ft.	85.60 7.95	3875.65 360.20
c)	22 SWG (1.21 mm.) thick sheet roofing	Sq.m. Sq.ft.	85.60 7.95	3581.00 332.80
d)	24 SWG (1.06 mm.) thick sheet roofing	Sq.m. Sq.ft.	85.60 7.95	3348.85 311.25
e)	26 SWG (0.97 mm.) thick sheet roofing	Sq.m. Sq.ft.	85.60 7.95	3197.10 297.15
13-19	Extra for fixing of G.I. corrugated or plain sheets on curved frame surface to a minimum radius of 5 ft. (1.5m) in ground floor	Sq.m. Sq.ft.	45.75 4.25	45.75 4.25
13-20	Providing and fixing corrugated asbestos cement sheets roofing 1/4" (6.4mm) thick with G.I. Hooks, bolts and G.I. or bitumen washers without valleys and ridges excluding the cost of frame work in ground floor.	Sq.m. Sq.ft.	86.60 8.05	1306.15 121.40
13-21	Providing and fixing corrugated asbestos cement sheet coloured roofing 5/32" (4mm) thick with G.I. Hooks, bolts and G.I. Or bitumen washers, without valleys and ridges excluding the cost of frame work in first floor.	Sq.m. Sq.ft.	86.60 8.05	1306.15 121.40
13-22	Providing and fixing corrugated G.I. sheet ridges 6 inches (150mm) girth and laps on either side with G.I. bolts, nuts, limpets and bitumen washers in ground floor.			
a)	18 SWG (1.41 mm) G.I. corrugated sheet ridge	Sq.m. Sq.ft.	247.95 23.05	2551.40 237.10
b)	20 SWG (1.31 mm) G.I. corrugated sheet ridge	Sq.m. Sq.ft.	247.95 23.05	2177.30 202.35
c)	22 SWG (1.21 mm) G.I. corrugated sheet ridge	Sq.m. Sq.ft.	247.95 23.05	1896.60 176.25
d)	24 SWG (1.06 mm) G.I. corrugated sheet ridge	Sq.m. Sq.ft.	247.95 23.05	1644.00 152.80
e)	26 SWG (0.97 mm) G.I. corrugated sheet ridge	Sq.m. Sq.ft.	247.95 23.05	1466.25 136.25
13-23	Providing and fixing fiber glass corrugated sheet with G.I. bolts, nuts, limpets and bitumen washers in ground floor.	Sq.m. Sq.ft.	247.95 23.05	4525.00 420.55
13-24	Providing and fixing plain G.I. sheet ridges 6 inches (150mm) girth and laps on either side with G.I. hooks, nuts, limpets and bitumen washers in ground floor.			
a)	18 SWG (1.41 mm) plain corrugated sheet ridge	Sq.m.	247.95	2413.30

Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
		Sq.ft.	23.05	224.30



Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
b)	20 SWG (1.31mm) plain corrugated sheet ridge	Sq.m.	247.95	2047.15
		Sq.ft.	23.05	190.25
c)	22 SWG (1.21mm) plain corrugated sheet ridge	Sq.m.	247.95	1752.45
		Sq.ft.	23.05	162.85
d)	24 SWG (1.06mm) plain corrugated sheet ridge	Sq.m.	247.95	1520.25
		Sq.ft.	23.05	141.30
e)	26 SWG (0.97 mm) plain corrugated sheet ridge	Sq.m.	247.95	1368.45
		Sq.ft.	23.05	127.20
13-25	Providing and fixing asbestos cement ridge two pieces close fitting or plain wing adjustable, 1/4 inch (6.4mm) thick with bolts and nuts in ground floor	R.M.	13.35	584.90
		R.ft.	4.05	178.30
13-26	Providing and fixing asbestos cement ridge two pieces close fitting or plain wing adjustable, 5/32" (4mm) thick with bolts and nuts in ground floor	R.M.	13.35	559.05
		R.ft.	4.05	170.40
13-27	Providing and fixing A.C. ridge plain angular one piece including bolts and nuts in ground floor	R.M.	13.35	584.90
		R.ft.	4.05	178.30
13-28	Providing and fixing two piece adjustable asbestos cement ridge finials in any floor at any height with bolts and nuts.			
a)	Grey Colour	Each	86.60	300.80
b)	Other than grey colour	Each	86.60	306.00
13-29	Providing and fixing plain galvanized iron gutters 18 inches (450mm) girth with bolts and nuts in ground floor			
a)	18 SWG (1.41mm) thick G.I. sheet gutter	R.M.	52.45	1084.10
		R.ft.	16.00	330.45
b)	20 SWG (1.31mm) thick G.I. sheet gutter	R.M.	52.45	933.60
		R.ft.	16.00	284.55
c)	22 SWG (1.21mm) thick G.I. sheet gutter	R.M.	52.45	812.50
		R.ft.	16.00	247.65
13-30	Providing and fixing 22 SWG (1.21mm) G.I. sheet gutter semi circular 12 inches (300mm) diameter.	R.M.	93.35	763.70
		R.ft.	28.45	232.80
13-31	Providing and fixing A.C. valley gutters size 9" x 6" (229mm x 152mm) and 1/4" (6.4mm) thick in ground floor	R.M.	58.55	1053.95
		R.ft.	17.85	321.25
13-32	Providing and fixing 1/4" (6.4mm) thick plain asbestos cement sheet ceiling on wooden frame with deodar wood beading 2" x 1/2" (51mm x 13mm) of required shape fixed with screws perforated in corners if required but excluding the cost of frame in ground floor	Sq.m.	103.45	1026.30
		Sq.ft.	9.60	95.40

Sr.No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
13-33 a)	Providing and fixing 1/2" (13mm) thick soft board ceiling of 600 kg per Cu.m. density with deodar wood beading 2" x 1/2" (51mm x 13mm) of required shape fixed with screws perforated in corners if required but excluding the cost of frame in ground floor	Sq.m.	103.45	496.30
		Sq.ft.	9.60	46.10
b)	Same as Item 13-32 but for chip board 1/2" (13mm) thick instead of soft board	Sq.m.	103.45	563.85
		Sq.ft.	9.60	52.40
c)	Same as Item 13-32 but for hard board 1/4" (6mm) thick instead of soft board	Sq.m.	103.45	107.95
		Sq.ft.	9.60	10.05
13-34	Providing and fixing thermopore sheet ceiling on wooden frame with deodar wood beading 2" x 1/2" (51mm x 13mm) of required shape, fixed with screws perforated in corners if required but excluding the cost of frame in ground floor			
a)	1/2 inch (13mm) thick thermopore sheet ceiling	Sq.m.	138.60	360.25
		Sq.ft.	12.90	33.50
b)	1 inch (25 mm) thick thermopore sheet ceiling	Sq.m.	138.60	392.05
		Sq.ft.	12.90	36.45
c)	1-1/2 inch (38 mm) thick thermopore sheet	Sq.m.	138.60	439.80
		Sq.ft.	12.90	40.85
13-35	Providing and fixing hessian cloth ceiling with wooden beading 2"x1/2" (50mm x13mm) in ground floor	Sq.m.	64.65	260.15
		Sq.ft.	6.00	24.20
13-36	Providing, fixing and hoisting best quality wood ceiling frame of required section including providing approved anti-termites treatment			
a)	Deodar wood	Cu.m.	912.55	1465.40
		Cu.ft.	25.85	41.50
b)	Partal wood	Cu.m.	912.55	1210.70
		Cu.ft.	25.85	34.30
c)	Kail wood	Cu.m.	912.55	1381.00
		Cu.ft.	25.85	39.10
13-37	Extra labour for erection of G.I.corrugated sheets, plain sheets or asbestos cement sheet roofing, above 20 ft. (6 m) height in difficult position, including lifting with care and special scaffolding along live electric wire.	Sq.m.	23.55	23.55
		Sq.ft.	2.20	2.20
13-38	Supplying and laying twin plain G.I. sheet 20 SWG (1.31 mm) painted with hot bitumen 1.65 kg/sq.m. with polythene film in between 300 gauge (0.03 mm) to provide a sliding joint under the bearing of the beams including 3 inch (75 mm) long three nos. bars to act as holdfasts on walls and beams.	Sq.m.	69.35	3211.20
		Sq.ft.	6.45	298.45
13-39	Providing and laying first class tile roof insulation comprising single layer of tiles 9"x 4-1/2"x 1-1/2" grouted with cement sand mortar 1:3 laid over 2 inch (50mm) thick earth including mud plaster over thermopore sheet over polythene sheet 300gauge (0.03mm) over a layer of hot bitumen coating, complete in all respect.			
a)	Using thermopore sheet 1/2 inch (13mm) thick.	Sq.m.	275.70	1137.75
		Sq.ft.	25.60	105.75