


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6064.35 171.75
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5967.25 169.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5911.65 167.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5870.75 166.25
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4720.70 133.70
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4637.80 131.35
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4590.15 130.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4554.90 129.00
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5166.80 146.35
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5069.05 143.55
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5013.45 142.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4972.50 140.80
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4492.20 127.20
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4368.45 123.70
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4295.75 121.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4243.45 120.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6535.95 185.10
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6456.20 182.85
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6359.65 180.10
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6302.85 178.50
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6263.15 177.40
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5083.85 144.00
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5015.30 142.05
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4932.40 139.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4883.55 138.30
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4849.50 137.35
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5603.25 158.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5523.45 156.45
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5426.95 153.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5370.15 152.10
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5330.40 150.95
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4889.00 138.45
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4786.80 135.55

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4661.80
		Cu.ft.	36.95	132.00
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4590.35
		Cu.ft.	36.95	130.00
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4538.05
		Cu.ft.	36.95	128.50
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6355.35
		Cu.ft.	71.55	180.00
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6258.85
		Cu.ft.	71.55	177.25
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6202.05
		Cu.ft.	71.55	175.65
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6162.30
		Cu.ft.	71.55	174.50
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	5018.40
		Cu.ft.	59.05	142.10
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4935.50
		Cu.ft.	59.05	139.80
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4887.85
		Cu.ft.	59.05	138.45
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4852.55
		Cu.ft.	59.05	137.45
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5436.05
		Cu.ft.	53.90	153.95
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5339.50
		Cu.ft.	53.90	151.20
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5283.90
		Cu.ft.	53.90	149.65
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5244.20
		Cu.ft.	53.90	148.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4470.25 126.60
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4346.45 123.10
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4275.00 121.05
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4222.70 119.60
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
<b>a) 4" (100 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6823.90 193.25
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6745.30 191.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6648.80 188.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6593.20 186.70
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6552.25 185.55
<b>b) 6" (150 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5379.10 152.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5310.55 150.40
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5227.65 148.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5180.00 146.70
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5145.95 145.75
<b>c) 8" (200 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5266.35 149.15
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5186.60 146.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5090.05 144.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5034.45
		Cu.ft.	36.95	142.60
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4994.75
		Cu.ft.	36.95	141.45
				
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4864.60
		Cu.ft.	36.95	137.75
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4763.60
		Cu.ft.	36.95	134.90
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4639.85
		Cu.ft.	36.95	131.40
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4567.15
		Cu.ft.	36.95	129.35
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4516.10
		Cu.ft.	36.95	127.90
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80