


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6097.55 172.70
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6001.15 169.95
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5944.35 168.35
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5904.65 167.20
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4745.45 134.40
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4662.50 132.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4614.85 130.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4579.60 129.70
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5196.75 147.20
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5100.20 144.45
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5043.40 142.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5003.65 141.70
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4518.95 128.00
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4393.95 124.45
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4321.25 122.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4270.20 120.95

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6722.05 190.35
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6642.10 188.10
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6545.55 185.35
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6489.95 183.80
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6449.05 182.65
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5223.05 147.90
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5154.35 145.95
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	5071.40 143.65
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	5023.75 142.30
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4988.50 141.30
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5773.10 163.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5693.15 161.25
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5596.65 158.50
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5539.80 156.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5500.10 155.75
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5030.30 142.45
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4927.85 139.55

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4802.85
		Cu.ft.	36.95	136.00
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4730.15
		Cu.ft.	36.95	133.95
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4679.10
		Cu.ft.	36.95	132.50
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6388.05
		Cu.ft.	71.55	180.90
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6291.55
		Cu.ft.	71.55	178.20
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6235.95
		Cu.ft.	71.55	176.60
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6195.00
		Cu.ft.	71.55	175.45
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	5043.10
		Cu.ft.	59.05	142.80
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4960.20
		Cu.ft.	59.05	140.50
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4912.55
		Cu.ft.	59.05	139.15
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4878.50
		Cu.ft.	59.05	138.15
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5465.95
		Cu.ft.	53.90	154.80
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5370.65
		Cu.ft.	53.90	152.10
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5313.85
		Cu.ft.	53.90	150.50
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5274.15
		Cu.ft.	53.90	149.35

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4495.75 127.30
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4372.00 123.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4300.50 121.80
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4248.25 120.30
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	7009.95 198.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6930.00 196.25
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6833.45 193.55
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6777.90 191.95
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6738.15 190.85
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5518.30 156.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5449.55 154.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5367.85 152.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5319.00 150.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5284.95 149.65
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5435.00 153.90
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5355.05 151.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5259.75 148.95



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5202.95
		Cu.ft.	36.95	147.35
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5163.20
		Cu.ft.	36.95	146.20
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	5005.90
		Cu.ft.	36.95	141.75
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4903.45
		Cu.ft.	36.95	138.85
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4779.65
		Cu.ft.	36.95	135.35
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4706.95
		Cu.ft.	36.95	133.30
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4655.90
		Cu.ft.	36.95	131.85
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80