

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| 29-1 | Rough dressing of the area for lawn including picking stones, pebbles, stubble, grass roots and other injurious matters and breaking of clods including disposal of rubbish within 300 ft (90m or 3 chains). | Sq.m. | 12.70 | 12.70 |
| | | Sq.ft. | 1.20 | 1.20 |
| 29-2 | Supplying and stacking well decayed cowdung manure from approved source including all leads and lifts. | Cu.m. | - | 275.70 |
| | | Cu.ft. | - | 7.80 |
| 29-3 | Spreading cowdung manure and mixing the same upto a depth of 4" (100mm) in the prepared bed including breaking clods, dressing for grassing including disposal of rubbish upto 300 ft (90 m or 3chains). | Cu.m. | 95.15 | 95.15 |
| | | Cu.ft. | 2.70 | 2.70 |
| 29-4 | Supplying and stacking well decayed sewage manure from approved source including all leads and lifts. | Cu.m. | - | 281.85 |
| | | Cu.ft. | - | 8.00 |
| 29-5 | Spreading sewage manure in uniform thickness in the prepared bed including mixing with original soil upto and depth including breaking clods and dressing for grassing including disposal of rubbish upto 300ft. (90m. or 3 chain) | Cu.m. | 79.30 | 79.30 |
| | | Cu.ft. | 2.25 | 2.25 |
| 29-6 | Supplying and stacking approved garden soil (sweet earth) free from salts, pebbles and grass roots including all leads and lifts. | Cu.m. | - | 379.85 |
| | | Cu.ft. | - | 10.75 |
| 29-7 | Spreading approved garden soil (sweet earth) in uniform thickness including mixing and breaking clods and dressing for grassing including disposal of rubbish within 300 ft. (90m or 3 chains). | Cu.m. | 79.30 | 79.30 |
| | | Cu.ft. | 2.25 | 2.25 |
| 29-8 | Supplying and stacking approved quality sand free from salts, pebbles, grass roots including all leads and lifts. | Cu.m. | - | 902.80 |
| | | Cu.ft. | - | 25.55 |
| 29-9 | Spreading approved quality sand uniform thickness and mixing the sand, breaking clods, and dressing for grassing including disposal of rubbish within 300 ft (90m. or 3 chains). | Cu.m. | 209.35 | 209.35 |
| | | Cu.ft. | 5.95 | 5.95 |
| 29-10 | Dressing upto depth of 4" (100 mm) and preparing the bed for final finishing including sprinkling water, raking and rubbing. | Cu.m. | 63.45 | 63.45 |
| | | Cu.ft. | 1.80 | 1.80 |
| 29-11 | Supplying and fixing of approved quality live local grass in shape of | Sq.m. | 12.70 | 238.95 |
| | | Sq.ft. | 1.18 | 22.20 |
| 29-12 | Providng and fixing of Grassing by dibbing live grass roots 3" (75 mm) apart including watering, weeding till such time the grass is set and becomes green and is fit for mowing (2kg for 1Sq. Ft. area). | Sq.m. | 42.46 | 43.56 |
| | | Sq.ft. | 3.95 | 4.05 |
| 29-13 | Supplying stone boulders of approved size and shape including all leads and lifts. | | | |
| a) | Stone boulder 9" (230 mm) size | Cu.m. | - | 208.40 |
| | | Cu.ft. | - | 5.90 |
| b) | Stone boulder 6" (150 mm) size | Cu.m. | - | 201.90 |
| | | Cu.ft. | - | 5.70 |
| c) | Stone boulder 3" to 4" (75mm to 100mm) size | Cu.m. | - | 195.40 |
| | | Cu.ft. | - | 5.54 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|------|------------|-----------|
| | | | Labour | Composite |
| 29-14 | Providing and fixing perforated standard bitumen drums for tree guards of approved design including painting in black and white. | Each | - | 911.05 |
| 29-15 | Providing and fixing 2" (50 mm) thick R.C.C. tree guards 48" x 30" x 30" (1.2 m x 0.75 m x 0.75 m) clear as per approved design and drawings including the cost of reinforcement and 3 coats of white washing | Each | 693.55 | 2970.35 |
| 29-16 | Providing and fixing 1:3:6 cement concrete solid block masonry 6" (150mm) thick honey combed, in tree guards average 5 ft (1.5 m) dia & 5 ft (1.5 m) high including foundation set in 1:6 cement sand mortar including curing and 3 coats of white washing (outside) as per approved design and drawings. | Each | 317.20 | 2314.95 |
| 29-17 | Providing and fixing first class burnt brick 4.5" (114 mm) thick masonry honey combed in tree guards average 5 ft (1.5 m) dia and 5 ft (1.5m) high including foundation set in 1:6 cement mortar including curing and 3 coats of white washing (outside) as per approved design and drawings. | Each | 253.75 | 4315.00 |
| 29-18 | Supplying and fixing 48" x 30" x 30" (1.2m x 0.75m x 0.75m) clear size frame in approved design and drawings of angle iron 18" x 18" x 1/4" (38mm x 38mm x 6mm) including painting and barbed wire in tree guards of required shape. | Each | 3025.75 | 5958.80 |
| 29-19 | Providing and fixing 48" x 30" x 30" (1.2m x 0.75m x 0.75m) clear size frame in approved design and drawings of shisham wood 2"x2" (50mm x 50mm) posts and frame with barbed wire in tree guards of required shape. | Each | 228.15 | 2635.80 |
| 29-20 | Providing and fixing G.I. barbed wire fencing with two to four points to the posts of any description with hooks and binding wire excluding cost of posts. | Kg. | 49.80 | 202.30 |
| | | Lbs. | 22.60 | 91.75 |