


| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-1 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2167.55 61.40 | 6625.50 187.65 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2167.55 61.40 | 6525.60 184.80 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2167.55 61.40 | 6467.00 183.15 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2167.55 61.40 | 6426.00 182.00 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1729.65 49.00 | 5147.80 145.80 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1729.65 49.00 | 5062.25 143.35 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1729.65 49.00 | 5013.05 141.95 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1729.65 49.00 | 4976.70 140.95 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1578.90 44.70 | 5694.25 161.25 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1578.90 44.70 | 5594.65 158.45 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1578.90 44.70 | 5536.05 156.80 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1578.90 44.70 | 5495.05 155.60 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1278.25 36.20 | 4983.95 141.15 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1278.25 36.20 | 4856.25 137.55 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1278.25 36.20 | 4781.25 135.40 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1278.25 36.20 | 4727.30 133.90 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-2 | Same as item 10-1 but in 1:2:4 concrete hollow block masonry. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2167.55 61.40 | 7036.15 199.25 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2167.55 61.40 | 7053.15 199.75 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2167.55 61.40 | 6953.55 196.95 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2167.55 61.40 | 6896.15 195.30 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2167.55 61.40 | 6853.95 194.10 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1729.65 49.00 | 5454.50 154.45 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1729.65 49.00 | 5469.05 154.90 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1729.65 49.00 | 5383.50 152.45 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1729.65 49.00 | 5334.30 151.05 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1729.65 49.00 | 5297.95 150.05 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1578.90 44.70 | 6066.30 171.80 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1578.90 44.70 | 6084.50 172.30 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1578.90 44.70 | 5983.70 169.45 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1578.90 44.70 | 5926.30 167.85 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1578.90 44.70 | 5884.10 166.65 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1278.25 36.20 | 5283.35 149.65 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1278.25 36.20 | 5305.20 150.25 |



| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1278.25 | 5177.50 |
| | | Cu.ft. | 36.20 | 146.65 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1278.25 | 5102.50 |
| | | Cu.ft. | 36.20 | 144.50 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1278.25 | 5048.55 |
| | | Cu.ft. | 36.20 | 143.00 |
| 10-3 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2473.35 | 6901.70 |
| | | Cu.ft. | 70.05 | 195.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2473.35 | 6802.10 |
| | | Cu.ft. | 70.05 | 192.65 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2473.35 | 6744.70 |
| | | Cu.ft. | 70.05 | 191.00 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2473.35 | 6702.50 |
| | | Cu.ft. | 70.05 | 189.80 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2035.40 | 5431.60 |
| | | Cu.ft. | 57.65 | 153.85 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2035.40 | 5346.05 |
| | | Cu.ft. | 57.65 | 151.40 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2035.40 | 5296.85 |
| | | Cu.ft. | 57.65 | 150.00 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2035.40 | 5261.75 |
| | | Cu.ft. | 57.65 | 149.00 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1861.80 | 5951.50 |
| | | Cu.ft. | 52.75 | 168.55 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1861.80 | 5851.90 |
| | | Cu.ft. | 52.75 | 165.75 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1861.80 | 5794.55 |
| | | Cu.ft. | 52.75 | 164.10 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1861.80 | 5753.55 |
| | | Cu.ft. | 52.75 | 162.95 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1278.25 36.20 | 4959.55 140.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1278.25 36.20 | 4831.85 136.85 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1278.25 36.20 | 4758.05 134.75 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1278.25 36.20 | 4704.10 133.20 |
| 10-4 | Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry. | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2473.35 70.05 | 7310.20 207.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2473.35 70.05 | 7327.20 207.50 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2473.35 70.05 | 7228.80 204.70 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2473.35 70.05 | 7170.20 203.05 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2473.35 70.05 | 7129.20 201.90 |
| b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2035.40 57.65 | 5737.05 162.50 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2035.40 57.65 | 5751.65 162.90 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2035.40 57.65 | 5666.10 160.45 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2035.40 57.65 | 5616.90 159.05 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2035.40 57.65 | 5580.55 158.05 |
| c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1278.25 36.20 | 5733.90 162.40 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1278.25 36.20 | 5750.90 162.85 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1278.25 36.20 | 5651.30 160.05 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|--------|------------|-----------|
| | | | Labour | Composite |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1278.25 | 5592.70 |
| | | Cu.ft. | 36.20 | 158.40 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1278.25 | 5551.70 |
| | | Cu.ft. | 36.20 | 157.25 |
|  | | | | |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1278.25 | 5257.70 |
| | | Cu.ft. | 36.20 | 148.90 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1278.25 | 5279.60 |
| | | Cu.ft. | 36.20 | 149.50 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1278.25 | 5151.85 |
| | | Cu.ft. | 36.20 | 145.90 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1278.25 | 5076.85 |
| | | Cu.ft. | 36.20 | 143.80 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1278.25 | 5024.15 |
| | | Cu.ft. | 36.20 | 142.30 |
| 10-5 | Extra for hollow block masonry in first floor superstructure. | Cu.m. | 443.25 | 443.25 |
| | | Cu.ft. | 12.55 | 12.55 |
| 10-6 | Extra for hollow block masonry in every additional floor above first floor. | Cu.m. | 359.95 | 359.95 |
| | | Cu.ft. | 10.20 | 10.20 |
| 10-7 | Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 83.55 | 98.15 |
| | | Cu.ft. | 2.35 | 2.80 |