

| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|---|-----------------|-------------------|--------------------|-------------------|
| | | | Labour | Composite | |
| 9-1 | Providing and laying 1:4:8 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 3/4" (19mm) & down gauge in foundation, basement and plinth including scaffolding, raking out joints and curing. | | | | 9.2 9.3 9.8 |
| | a) 4" (100 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,633.52 272.85 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,850.95 80.75 | 8,610.38 243.85 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,466.78 268.10 | |
| | b) 6" (150 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,717.22 246.90 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,636.91 244.60 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,570.04 242.70 | |
| | c) 8" (200 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,825.79 249.95 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,717.66 246.90 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,659.06 245.25 | |
| | d) 12" (300 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,434.34 238.85 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,324.53 235.75 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,186.27 231.85 | |
| 9-2 | Same as in item 9-1 but in 1:3:6 cement concrete block | | | | 9.2 9.3 9.8 |
| | a) 4" (100 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,997.38 283.15 | |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,817.88 278.05 | |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,734.37 275.70 | |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,850.95 80.75 | 9,659.45 273.55 | |



| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|--|-----------------|-------------------|---------------------|-------------------|
| | | | Labour | Composite | |
| | b) 6" (150 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,985.60 254.50 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,819.90 249.80 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,733.74 247.35 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1,901.20 53.85 | 8,313.62 235.45 | |
| | c) 8" (200 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,025.75 57.35 | 9,138.27 258.80 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,957.79 253.70 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,871.98 251.25 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,025.75 57.35 | 8,811.12 249.55 | |
| | d) 12" (300 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,725.54 247.10 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,254.03 233.75 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,243.55 233.45 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1,622.80 45.95 | 8,126.15 230.15 | |
| 9-3 | Same as in item 9-1 but in 1:2:4 cement concrete block | | | | 9.2 9.3 9.8 |
| | a) 4" (100 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2,850.95 80.75 | 11,129.16 315.20 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,850.95 80.75 | 11,013.93 311.90 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,850.95 80.75 | 10,849.14 307.25 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,850.95 80.75 | 10,757.63 304.65 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,850.95 80.75 | 10,683.94 302.60 | |



| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|--|--|--------|------------|-----------|-------------------|
| | | | Labour | Composite | |
| b) 6" (150 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1,901.20 | 10,133.04 | |
| | | Cu.ft. | 53.85 | 286.95 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1,901.20 | 10,018.01 | |
| | | Cu.ft. | 53.85 | 283.70 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1,901.20 | 9,851.61 | |
| | | Cu.ft. | 53.85 | 279.00 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1,901.20 | 9,753.47 | |
| | | Cu.ft. | 53.85 | 276.20 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1,901.20 | 9,679.64 | |
| | | Cu.ft. | 53.85 | 274.15 | |
| c) 8" (200 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 2,025.75 | 10,275.73 | |
| | | Cu.ft. | 57.35 | 291.00 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 2,025.75 | 10,164.16 | |
| | | Cu.ft. | 57.35 | 287.85 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 2,025.75 | 9,997.74 | |
| | | Cu.ft. | 57.35 | 283.15 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 2,025.75 | 9,895.89 | |
| | | Cu.ft. | 57.35 | 280.25 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 2,025.75 | 9,809.80 | |
| | | Cu.ft. | 57.35 | 277.80 | |
| d) 12" (300 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1,622.80 | 9,870.42 | |
| | | Cu.ft. | 45.95 | 279.55 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1,622.80 | 9,747.09 | |
| | | Cu.ft. | 45.95 | 276.05 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1,622.80 | 9,590.22 | |
| | | Cu.ft. | 45.95 | 271.60 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1,622.80 | 9,486.38 | |
| | | Cu.ft. | 45.95 | 268.65 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1,622.80 | 9,422.46 | |
| | | Cu.ft. | 45.95 | 266.85 | |
| 9-4 | Extra for every 6.5 ft (2 m.) or part thereof in foundation and basement masonry deeper than 6.5 ft (2 m.) | Cu.m. | - | 176.95 | 9.2 |
| | | Cu.ft. | - | 5.00 | 9.3 |
| 9-5 | Extra for every 5 ft (1.5 m) or part thereof in foundation and basement masonry deeper than 5 ft (1.5 m) | Cu.m. | - | 234.20 | 9.2 |
| | | Cu.ft. | - | 6.65 | 9.3 |
| | | | | | 9.8 |




| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|--|-----------------|--------------------|---------------------|-------------------|
| | | | Labour | Composite | |
| 9-6 | Providing and laying 1:4:8 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 3/4" (19mm) and down gauge in ground floor super-structure including scaffolding, raking out joints and curing. | | | | 9.2 9.3 9.8 |
| | a) 4" (100 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,336.53 321.05 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 6,361.50 180.15 | 10,177.87 288.25 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,162.97 316.15 | |
| | b) 6" (150 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,462.00 126.35 | 10,119.86 286.60 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,462.00 126.35 | 8,996.01 254.75 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,462.00 126.35 | 9,961.59 282.10 | |
| | c) 8" (200 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,668.40 132.20 | 10,122.71 286.70 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,668.40 132.20 | 8,976.73 254.25 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,668.40 132.20 | 9,965.95 282.25 | |
| | d) 12" (300 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 3,245.60 91.90 | 9,071.26 256.90 | |
| | ii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 3,245.60 91.90 | 7,992.65 226.35 | |
| | iii) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 3,245.60 91.90 | 8,900.23 252.05 | |
| 9-7 | Same as item 9-6 but in 1:3:6 cement concrete block | | | | 9.2 9.3 9.8 |
| | a) 4" (100 mm) thick solid block masonry | | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,950.50 338.45 | |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,787.94 333.85 | |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,696.27 331.25 | |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 6,361.50 180.15 | 11,646.29 329.85 | |



| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|---|-----------------|--------------------|---------------------|-------------------|
| | | | Labour | Composite | |
| | b) 6" (150 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 4,462.00 126.35 | 10,564.50 299.20 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,462.00 126.35 | 10,405.96 294.70 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,462.00 126.35 | 10,351.00 293.15 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,462.00 126.35 | 10,265.25 290.70 | |
| | c) 8" (200 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 4,668.40 132.20 | 10,614.67 300.60 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,668.40 132.20 | 10,463.97 296.35 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,668.40 132.20 | 10,364.65 293.55 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,668.40 132.20 | 10,299.01 291.65 | |
| | d) 12" (300 mm) thick solid block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 3,245.60 91.90 | 9,493.59 268.85 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 3,245.60 91.90 | 9,329.99 264.25 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 3,245.60 91.90 | 9,236.75 261.60 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 3,245.60 91.90 | 9,165.20 259.55 | |
| 9-8 | Same as item 9-6 but in 1:2:4 cement concrete block | | | | 9.2 |
| | a) 4" (100 mm) thick solid block masonry | | | | 9.3 |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 6,361.50 180.15 | 13,065.43 370.00 | 9.8 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 6,361.50 180.15 | 12,955.24 366.90 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 6,361.50 180.15 | 12,799.57 362.50 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 6,361.50 180.15 | 12,713.08 360.05 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 6,361.50 180.15 | 12,644.34 358.10 | |



| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---|---|-----------------|--------------------|---------------------|-------------------|
| | | | Labour | Composite | |
|  | | | | | |
| b) 6" (150 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 4,462.00 126.35 | 11,706.79 331.55 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 4,462.00 126.35 | 11,598.32 328.45 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,462.00 126.35 | 11,400.48 322.85 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,462.00 126.35 | 11,339.61 321.15 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,462.00 126.35 | 11,277.19 319.40 | |
| c) 8" (200 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 4,668.40 132.20 | 11,759.82 333.05 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 4,668.40 132.20 | 11,639.68 329.65 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 4,668.40 132.20 | 11,484.37 325.25 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 4,668.40 132.20 | 11,382.97 322.35 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 4,668.40 132.20 | 11,327.94 320.80 | |
| d) 12" (300 mm) thick solid block masonry | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 3,245.60 91.90 | 10,632.33 301.10 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 3,245.60 91.90 | 10,506.45 297.55 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 3,245.60 91.90 | 10,375.38 293.85 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 3,245.60 91.90 | 10,263.04 290.65 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 3,245.60 91.90 | 10,065.14 285.05 | |
| 9-9 | Extra for masonry of any description in pillars and columns of any shape over the rate of respective item | % | - | 9.00 | 9.2 9.3 9.8 |
| 9-10 | Extra for masonry of any description in arches, architrave coping and cornice of any shape over the rate of the | % | - | 16.08 | 9.3 9.8 |
| 9-11 | Extra for masonry of any description of bonding old and new masonry including making recesses in old masonry. The measurement will be made for the actual new masonry | Cu.m. Cu.ft. | 2,590.05 73.35 | 2,590.05 73.35 | 9.2 9.3 9.8 |

| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|---|--------|------------|-----------|-------------------|
| | | | Labour | Composite | |
| 9-12 | Extra for work in first floor above ground floor. | Cu.m. | 524.40 | 524.40 | 9.2 |
| | | Cu.ft. | 14.85 | 14.85 | 9.3 |
| | | | | | 9.8 |
| 9-13 | Extra for work in every additional floor above first floor | Cu.m. | 420.35 | 420.35 | 9.2 |
| | | Cu.ft. | 11.90 | 11.90 | 9.3 |
| | | | | | 9.8 |
| 9-14 | Extra for work in arches in first floor above ground floor | Cu.m. | 654.50 | 654.50 | 9.2 |
| | | Cu.ft. | 18.55 | 18.55 | 9.3 |
| | | | | | 9.8 |
| 9-15 | Extra for work in arches in every additional floor above first | Cu.m. | 550.45 | 550.45 | 9.2 |
| | | Cu.ft. | 15.60 | 15.60 | 9.3 |
| | | | | | 9.8 |
| 9-16 | Extra for cement concrete solid block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 441.50 | 441.50 | 9.2 |
| | | Cu.ft. | 12.50 | 12.50 | 9.3 |
| | | | | | 9.8 |
| 9-17 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out | | | | 9.2 |
| | | | | | 9.3 |
| | | | | | 9.8 |
| | a) 4" (100 mm) thick hollow block masonry | | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. | 3,563.70 | 7,428.65 | |
| | | Cu.ft. | 100.95 | 210.40 | |
| | ii) Cement sand mortar 1 : 4 | Cu.m. | 3,563.70 | 7,314.70 | |
| | | Cu.ft. | 100.95 | 207.15 | |
| | iii) Cement sand mortar 1 : 5 | Cu.m. | 3,563.70 | 7,247.75 | |
| | | Cu.ft. | 100.95 | 205.25 | |
| | iv) Cement sand mortar 1 : 6 | Cu.m. | 3,563.70 | 7,199.55 | |
| | | Cu.ft. | 100.95 | 203.90 | |
| | b) 6" (150 mm) thick hollow block masonry | | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. | 2,376.50 | 6,100.55 | |
| | | Cu.ft. | 67.30 | 172.75 | |
| | ii) Cement sand mortar 1 : 4 | Cu.m. | 2,376.50 | 5,986.60 | |
| | | Cu.ft. | 67.30 | 169.55 | |
| | iii) Cement sand mortar 1 : 5 | Cu.m. | 2,376.50 | 5,919.60 | |
| | | Cu.ft. | 67.30 | 167.65 | |
| | iv) Cement sand mortar 1 : 6 | Cu.m. | 2,376.50 | 5,871.40 | |
| | | Cu.ft. | 67.30 | 166.30 | |
| | c) 8" (200 mm) thick hollow block masonry | | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. | 2,532.20 | 5,342.00 | |
| | | Cu.ft. | 71.70 | 151.30 | |
| | ii) Cement sand mortar 1 : 4 | Cu.m. | 2,532.20 | 5,244.15 | |
| | | Cu.ft. | 71.70 | 148.50 | |

| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|---|-----------------|--------------------|---------------------|-------------------|
| | | | Labour | Composite | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,532.20 71.70 | 5,186.60 146.90 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2,532.20 | 5,145.10 | |
| | | Cu.ft. | 71.70 | 145.70 | |
| | d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,028.50 57.45 | 5,272.05 149.30 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,028.50 57.45 | 5,124.65 145.15 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,028.50 57.45 | 5,038.90 142.70 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,028.50 57.45 | 4,977.30 140.95 | |
| 9-18 | Same as item 9-17 but in 1:2:4 concrete hollow block masonry. | | | | 9.2 |
| | a) 4" (100 mm) thick hollow block masonry | | | | 9.3 |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 3,563.70 100.95 | 8,169.30 231.35 | 9.8 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 3,563.70 100.95 | 4,557.65 129.10 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 3,563.70 100.95 | 4,443.70 125.85 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 3,563.70 100.95 | 4,376.70 123.95 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 3,563.70 100.95 | 4,328.50 122.60 | |
| | b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2,376.50 67.30 | 6,782.40 192.10 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,376.50 67.30 | 12,273.35 347.60 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,376.50 67.30 | 12,158.20 344.35 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,376.50 67.30 | 12,091.20 342.45 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,376.50 67.30 | 12,044.25 341.10 | |
| | c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2,532.20 71.70 | 5,906.90 167.30 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,532.20 71.70 | 9,654.90 273.45 | |

| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. | |
|---|--|--------|------------|-----------|-------------------|--|
| | | | Labour | Composite | | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 2,532.20 | 9,557.05 | 9.2 9.3 9.8 | |
| | | Cu.ft. | 71.70 | 270.65 | | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 2,532.20 | 9,499.45 | | |
| | | Cu.ft. | 71.70 | 269.05 | | |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 2,532.20 | 9,459.20 | | |
| | | Cu.ft. | 71.70 | 267.90 | | |
| d) 12" (300 mm) thick hollow block masonry | | | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 2,028.50 | 5,873.40 | | |
| | | Cu.ft. | 57.45 | 166.35 | | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 2,028.50 | 5,762.80 | | |
| | | Cu.ft. | 57.45 | 163.20 | | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 2,028.50 | 5,615.40 | | |
| | | Cu.ft. | 57.45 | 159.05 | | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 2,028.50 | 5,529.65 | | |
| | | Cu.ft. | 57.45 | 156.60 | | |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 2,028.50 | 5,468.05 | | |
| | | Cu.ft. | 57.45 | 154.85 | | |
| 9-19 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor | | | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2,945.15 | 7,807.95 | | |
| | | Cu.ft. | 83.40 | 221.15 | | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2,945.15 | 7,694.00 | | |
| | | Cu.ft. | 83.40 | 217.90 | | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2,945.15 | 7,628.25 | | |
| | | Cu.ft. | 83.40 | 216.05 | | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2,945.15 | 7,581.30 | | |
| | | Cu.ft. | 83.40 | 214.70 | | |
| b) 6" (150 mm) thick hollow block masonry | | | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2,065.74 | 6,459.25 | | |
| | | Cu.ft. | 58.50 | 182.95 | | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2,065.74 | 6,346.50 | | |
| | | Cu.ft. | 58.50 | 179.75 | | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2,065.74 | 6,279.55 | | |
| | | Cu.ft. | 58.50 | 177.85 | | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2,065.74 | 6,232.55 | | |
| | | Cu.ft. | 58.50 | 176.50 | | |



| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. Tech. Specs. |
|---------|--|-----------------|-------------------|--------------------|-------------------|
| | | | Labour | Composite | |
| | c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,161.30 61.20 | 5,732.30 162.35 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,161.30 61.20 | 9,953.60 281.90 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,161.30 61.20 | 9,896.05 280.25 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,161.30 61.20 | 9,855.80 279.10 | |
| | d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1,502.59 42.55 | 5,246.40 148.60 | |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1,502.59 42.55 | 5,099.05 144.40 | |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1,502.59 42.55 | 5,014.50 142.00 | |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1,502.59 42.55 | 4,952.90 140.25 | |
| 9-20 | Same as item 9-19 but in 1:2:4 cement concrete hollow block masonry. | | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2,945.15 83.40 | 8,544.95 242.00 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,945.15 83.40 | 6,082.35 172.25 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,945.15 83.40 | 5,968.40 169.05 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,945.15 83.40 | 5,902.65 167.15 | |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2,945.15 83.40 | 5,855.65 165.85 | |
| | b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2,065.74 58.50 | 6,293.50 178.25 | |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2,065.74 58.50 | 6,219.40 176.15 | |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2,065.74 58.50 | 6,122.75 173.40 | |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2,065.74 58.50 | 6,065.20 171.75 | |

