	<b>-</b>		Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
15-1	Coment plactor using Lawrencepur cand an soffite of coiling, cantilover				45.4
15-1	Cement plaster using Lawrencepur sand on soffits of ceiling, cantilever slabs, sides and soffits of beams, in basement and ground floor including making edges, corners and curing.	ı			15.1
a)	1/2 inch (13mm) thick cement sand plaster				
	1:2	Sq.m. Sq.ft.	137.35 12.75	322.80 30.00	
	1:3	Sq.m. Sq.ft.	137.35 12.75	299.45 27.85	
	1:4	Sq.m. Sq.ft.	137.35 12.75	273.85 25.45	
b)	3/8 inch (9.5 mm.) thick cement sand plaster				
	1:2	Sq.m. Sq.ft.	137.35 12.75	271.80 25.25	
	1:3	Sq.m. Sq.ft.	137.35 12.75	255.10 23.70	
	1:4	Sq.m. Sq.ft.	137.35 12.75	236.80 22.00	
c)	1/4 inch (6.4 mm.) thick cement sand plaster				
,	1:2	Sq.m. Sq.ft.	137.35 12.75	233.55 21.70	
	1:3	Sq.m.	137.35	221.85	
		Sq.ft.	12.75	20.60	
	1:4	Sq.m. Sq.ft.	137.35 12.75	209.05 19.45	
15-2	3/8 inch (9.5mm) thick cement plaster using Lawrencepur sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.				15.1
	1:2	Sq.m. Sq.ft.	116.35 10.80	249.70 23.20	
	1:3	Sq.m. Sq.ft.	116.35 10.80	233.00 21.65	
	1:4	Sq.m. Sq.ft.	116.35 10.80	214.70 19.95	
	1:5	Sq.m. Sq.ft.	116.35 10.80	204.05 18.95	
	1:6	Sq.m. Sq.ft.	116.35 10.80	199.90 18.60	

			Rat	te (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
45.0	4/2 inch (42mm) thick coment placter using Laurencenus and an				45.4
15-3	1/2 inch (13mm) thick cement plaster using Lawrencepur sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.				15.1
	1:2	Sq.m. Sq.ft.	123.45 11.45	342.44 31.85	
	1:3	Sq.m. Sq.ft.	123.45 11.45	316.44 29.40	
	1:4	Sq.m. Sq.ft.	123.45 11.45	288.00 26.75	
	1:5	Sq.m. Sq.ft.	123.45 11.45	271.39 25.20	
	1:6	Sq.m. Sq.ft.	123.45 11.45	254.06 23.60	
15-4	3/4 inch (19mm) thick cement plaster using Lawrencepur sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.				15.1
	1:2	Sq.m. Sq.ft.	128.10 11.90	401.00 37.25	
	1:3	Sq.m. Sq.ft.	128.10 11.90	366.15 34.05	
	1:4	Sq.m. Sq.ft.	128.10 11.90	327.90 30.45	
	1:5	Sq.m. Sq.ft.	128.10 11.90	305.60 28.40	
	1:6	Sq.m. Sq.ft.	128.10 11.90	289.70 26.90	
15-5	1 inch (25mm) thick cement plaster using Lawrencepur sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.				15.1
	1:2	Sq.m. Sq.ft.	155.30 14.45	519.35 48.25	
	1:3	Sq.m. Sq.ft.	155.30 14.45	472.75 43.95	
	1:4	Sq.m. Sq.ft.	155.30 14.45	421.65 39.20	
	1:5	Sq.m. Sq.ft.	155.30 14.45	391.85 36.40	
	1:6	Sq.m. Sq.ft.	155.30 14.45	370.55 34.45	
15-6	Extra for plaster of any description for every additional 5 ft.(1.5m.) height or part thereof beyond 15 ft. (4.5 m.)	Sq.m. Sq.ft.	68.05 6.30	84.40 7.85	

Sr. No.	Description	l lni4	Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
15-7	Providing ornamental moulding of approved design at the junction of slabs and walls in cement sand mortar 1:3 using Lawrencepur sand with 1.125 inch (28.5mm) average thickness consisting of 1 inch (25mm) undercoat and ().125 inch (3mm) thick finishing layer including curing in any floor	Sq.ft.	735.15 68.30	2,321.49 215.75	15.1
15-8	Providing and applying 3/4" (19mm) thick rough cast cement rendering comprising 3/8" (9.5mm) topping of 1 : 2 (one part cement & two part crushed aggregate 3/8" and down gauge) and base of 3/8" (9.5mm) thick rough plaster 1:4 in plinth and ground floor including finishing	Sq.ft.	197.55 18.35	427.00 39.70	15.6
15-9	Providing and applying 3/4" (19 mm) thick ornamental plaster with 1:3 cement sand mortar using Lawrencepur sand on walls, columns and slabs finished smooth in basement, plinth and first floor including curing	Sa.ft.	458.55 42.60	1,039.50 96.60	15.2
15-10	Making drip course 1/2"x 3/8" (13mm x 9.5mm) size under R.C.C. or cement concrete coping and sun shades in all floors including cost of cement sand mortar 1:3 using Lawrencepur sand and curing		27.60 8.40	58.50 17.85	
15-11	Making 1/2" (13mm) thick 1-1/2" to 2-1/2" (38mm to 64mm) wide plaster band with 1:3 cement sand mortar using Lawrencepur sand in all floors including curing.	R.M. R.ft.	35.40 10.80	81.50 24.85	
15-12	Making 1/2" (13mm) thick plaster band upto 4" (100mm) wide with 1:3 cement sand mortar using Lawrencepur sand in all floors including curing.	R.M. R.ft.	43.20 13.15	63.25 19.30	11.7(b)
15-13	Making 1/2" (13mm) thick 6" to 9" (150mm to 225mm) wide plaster band with 1:3 cement sand mortar using Lawrencepur sand in all floors including curing.	R.M. R.ft.	53.40 16.30	89.60 27.30	11.7(b)
15-14	Providing and mixing water proofing agent in cement mortar of any description in any floor				11.7(b)
	Same rate as in item 5-34 is applicable				15.1.4.4
15-15	Providing and mixing accelerating, retarding or wetting agent in cement sand mortar of any description in any floor				45 4 4 4
	Same rate as in item 5-31 to 5-33 is applicable				15.1.4.4
15-16	Extra if false pointing is required with lime/surkhi or pigment on plastered surface of any description in any floor.	Sq.m. Sq.ft.	84.15 7.80	95.55 8.90	
15-17	Extra if ruled pointing is required to give stone appearance on plastered surface of any description in any floor	Sq.m. Sq.ft.	84.15 7.80	236.64 22.00	
15-18	Extra if deep cut grooves of approved size and design are made on plastered surface of any description in any floor	Sq.m. Sq.ft.	126.25 11.75	362.79 33.70	
15-19	Extra for using washing soda in cement mortar of any description.	Kg. lb.	-	129.90 58.90	
15-20	Providing and mixing pigment in cement mortar of any description in any floor.	Kg. lb.	- -	514.36 233.30	
15-21	Extra for plaster of any description for overhead tank.				
a)	Upto 6 m. height.	Sq.m. Sq.ft.	19.37 1.80	57.26 5.30	

Sr. No.	Description	l lni4	Rat	e (Rs.)	Ref. Tech.
3r. NO.	Description	Unit	Labour	Composite	Specs.
b	Extra for every additional 5 ft.(1.5 m) height or part thereof	Sq.m.	89.50	102.90	
	Zana ioi ovoly additional o it.(1.6 m) hoight of part thoron	Sq.ft.	8.30	9.55	
15-22	Providing and fixing expanded metal or wire net lathing with 3/4" (19mm) cement plaster 1:4 using Lawrencepur sand in three layers including curing in any floor.				151.9.1
a)	With expanded metal 3/4" x 2-1/2" - 12 gauge (19mmx64mmx2.17mm)	Sq.m. Sq.ft.	608.90 56.60	1,946.20 180.85	
b	With wire netting 1-1/2" (38mm) mesh - 18 gauge (1.4mm) thick	Sq.m. Sq.ft.	420.80 39.10	1,313.05 122.05	15.1.9
15-23	Providing and applying 1/2" (13mm) thick 1 3 cement sand mortar under coat with mortar of plaster of paris or gypsum plaster in basement and ground floor including curing	Sq.m. Sq.ft.	123.45 11.45	277.45 25.80	15.10 15.1
15-24	Providing and fixing gypsum board with wire nails to wooden frame to receive gypsum plaster finishing coat in basement and ground floor but excluding the cost of wooden frame.				15.10.1
a	1/4" (6.4 mm) thick gypsum board	Sq.m. Sq.ft.	178.20 16.55	459.80 42.75	
b	3/8" (9.5 mm) thick gypsum board	Sq.m. Sq.ft.	178.20 16.55	515.95 47.95	
c)	1/2" (13 mm) thick gypsum board	Sq.m. Sq.ft.	178.20 16.55	572.05 53.15	
15-25	Providing and fixing insulating fibre board 1/2" (13 mm) thick with wire nails to wooden frame to receive gypsum plaster finishing coat in basement and ground floor but excluding the cost of wooden frame	Sq.m. Sq.ft.	178.20 16.55	5,350.80 497.30	15.10
15-26	Providing and applying 1/4" (6.4mm) thick gypsum plaster over a prepared base coat in basement and ground floor but excluding the cost of base coat.				15.10
a	1:4 (1 gypsum & 4 lime)	Sq.m. Sq.ft.	96.55 8.95	174.35 16.20	
b	1:3 (1 gypsum & 3 lime)	Sq.m. Sq.ft.	96.55 8.95	179.05 16.65	
15-27	Providing and applying cement plaster 1:2 using Lawrencepur sand with curing				15.3.5
a	1/4" (6.4 mm) thick	Sq.m. Sq.ft.	103.95 9.65	193.05 17.95	
b	1/2" (13 mm) thick	Sq.m. Sq.ft.	103.95 9.65	282.10 26.20	
15-28	Providing and laying 2" (50mm) thick stucco cement plaster 1:2:4 (1cement, 2sand, 4crush 1/2" and down gauge) using Lawrencepur sand in basement and ground floor including curing.	Sq.m. Sq.ft.	267.95 24.90	627.60 58.35	15.9

Sr. No.	Description	Unit	Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
15-29	Providing and laying machine sprayed plaster using cement and zero				15 1 5
13-29	number marble chips over a prepared roughened base coat in basement and ground floor but excluding the cost of base coat.				15.1.5
a)	1:1 (one cement and one marble chips)				
	1/2" Thick	Sq.m. Sq.ft.	79.50 7.40	464.25 43.15	
	1/4" Thick	Sq.m. Sq.ft.	79.50 7.40	272.80 25.35	
b)	1 : 1.5 (one cement and one & half marble chips)				
	1 : 1.5 (one cement and one & half marble chips)  1/2" Thick	Sq.m. Sq.ft.	79.50 7.40	452.05 42.00	
2)	1/4" Thick 1 : 2 (one cement and two marble chips)	Sq.m. Sq.ft.	79.50 7.40	266.70 24.80	
()	1/2" Thick	Sq.m.	79.50	443.95	
	1/2 THICK	Sq.ft.	7.40	41.25	
	1/4" Thick	Sq.m. Sq.ft.	79.50 7.40	262.65 24.40	
15-30	Providing floating coat of cement 1/32" (0.8 mm) thick including curing	Sq.m. Sq.ft.	73.00 6.80	107.35 10.00	15.1
15-31	Providing gobri leeping upto 1/8 inches (3.2mm) thick mixed with cowdung and clay using one part cowdung and one part clay at any height and in any floor				15.1.11
a)	On walls	Sq.m. Sq.ft.	20.10 1.85	21.20 1.95	
b)	Over floor or roof	Sq.m. Sq.ft.	14.85 1.40	15.90 1.50	
15-32	Mud plaster on walls mixed with cowdung, bhoosa and clay 1:1:2 (one part cowdung, one part bhoosa weighing 80 kg./cu.m. and two parts clay) in basement, plinth and ground floor.				15.1.11
a)	1/2" (13 mm) thick	Sq.m. Sq.ft.	107.05 9.95	125.70 11.70	
b)	3/4" (19 mm) thick	Sq.m. Sq.ft.	116.95 10.85	142.70 13.25	
c)	1" (25 mm) thick	Sq.m. Sq.ft.	129.00 12.00	162.00 15.05	
d)	1.25" (32 mm) thick	Sq.m. Sq.ft.	141.10 13.10	181.35 16.85	

C- N-	Danasiatian	l lm!4	Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
15-33	Mud plaster on floor mixed with cowdung, bhoosa and clay 1:1:2 (one				45 4 44
15-33	part cowdung, one part bhoosa weighing 80 kg./cu.m. and two parts clay) in basement, plinth and ground floor.				15.1.11
a)	1/2" (13 mm) thick	Sq.m. Sq.ft.	98.55 9.15	114.30 10.60	
b)	3/4" (19 mm) thick	Sq.m. Sq.ft.	104.10 9.65	126.65 11.75	
c)	1" (25 mm) thick	Sq.m. Sq.ft.	116.20 10.80	145.65 13.55	
d)	1.25" (32 mm) thick	Sq.m. Sq.ft.	128.25 11.90	164.65 15.30	
e)	Extra over item 15-33 (a to d) for roof	Sq.m. Sq.ft.	41.45 3.85	41.45 3.85	
15-34	Extra for plaster work of any description on first floor.				
a)	Upto 1/2 inch (13 mm) thick	Sq.m. Sq.ft.	112.40 10.45	129.25 12.00	
b)	Above 1/2 inch (13 mm) and upto 1 inch (25 mm) thick	Sq.m. Sq.ft.	119.75 11.15	137.70 12.80	
c)	Above 1 inch (25 mm) thick	Sq.m. Sq.ft.	155.65 14.45	178.95 16.65	
15-35	Extra for every additional floor above first floor for plaster work of any description.				
a)	Upto 1/2 inch (13 mm) thick	Sq.m. Sq.ft.	97.70 9.10	112.35 10.45	
b)	Above 1/2 inch (13 mm) and upto 1 inch (25 mm) thick	Sq.m. Sq.ft.	105.05 9.75	120.80 11.25	
c)	Above 1 inch (25 mm) thick	Sq.m. Sq.ft.	110.20 10.25	126.75 11.80	
	Pointing on brick work with cement sand mortar in plinth and ground floor including raking out joints and curing				15.2
a)	Flush pointing in cement sand mortar				
	1:2	Sq.m. Sq.ft.	191.85 17.85	423.36 39.35	
	1:3	Sq.m. Sq.ft.	191.85 17.85	415.73 38.65	
b)	Deep ruled pointing in cement sand mortar	0	054.05	007.40	
	1:2	Sq.m. Sq.ft.	251.25 23.35	397.19 36.90	
	1:3	Sq.m. Sq.ft.	251.25 23.35	383.43 35.65	

Sr. No.		Di-ti	I I and it	Rat	e (Rs.)	Ref. Tech.
Sr. No	).	Description	Unit	Labour	Composite	Specs.
	c)	Tuck or weather struck pointing in cement sand mortar 1:2	Sq.m.	183.15	254.95	
			Sq.ft.	17.00	23.70	
		1:3	Sq.m. Sq.ft.	183.15 17.00	246.75 22.95	
	d)	Extra for first floor	Sq.m. Sq.ft.	17.35 1.60	17.35 1.60	
	e)	Extra for every additional floor above first floor.	Sq.m. Sq.ft.	12.40 1.15	12.40 1.15	
15-37		plinth and ground floor including raking out joints and curing				15.2
	a)	Flush pointing in cement sand mortar				
		1:2	Sq.m. Sq.ft.	139.85 13.00	335.98 31.20	
		1:3	Sq.m. Sq.ft.	139.85 13.00	311.32 28.95	
	b)	Deep ruled pointing in cement sand mortar				
		1:2	Sq.m. Sq.ft.	170.80 15.85	337.05 31.30	
		1:3	Sq.m. Sq.ft.	170.80 15.85	326.15 30.30	
	c)	Tuck or weather struck pointing in cement sand mortar  1:2	Sq.m.	201.75	369.71	
		1.2	Sq.ft.	18.75	34.35	
		1:3	Sq.m. Sq.ft.	201.75 18.75	360.93 33.55	
	d)	Extra for first floor	Sq.m. Sq.ft.	14.85 1.40	14.85 1.40	
	e)	Extra for every additional floor above first floor.	Sq.m. Sq.ft.	12.40 1.15	12.40 1.15	
15-38		Pointing on stone work with cement sand mortar using Lawrencepur sand in plinth and ground floor including raking out joints and curing				15.2
	a)	Flush pointing in cement sand mortar				
		1:2	Sq.m. Sq.ft.	166.45 15.45	231.10 21.50	
		1:3	Sq.m. Sq.ft.	166.45 15.45	222.90 20.70	

Cr. No	Description.	He!t	Rat	te (Rs.)	Ref. Tech.	
Sr. No.	Description	Unit	Labour	Composite	Specs.	
	Door willed pointing in compart and morter					
· '	Deep ruled pointing in cement sand mortar	•	407.40	074.00		
	1:2	Sq.m. , Sq.ft.	197.40 18.35	271.80 25.25		
		. 3q.ii.	10.33	23.23		
	1:3	Sq.m.	197.40	262.35		
		Sq.ft.	18.35	24.40		
	(* ) min					
(	Tuck or weather struck pointing in cement sand mortar					
	1:2	Sq.m.	228.35	311.80		
	Constant Constant	Sq.ft.	21.20	29.00		
	1:3	Sq.m.	228.35	302.35		
	1:3	Sq.ft.	21.20	28.10		
	177 290 200					
(	Raised or cut pointing in cement sand mortar					
	1:2	Sq.m.	259.30	343.80		
		Sq.ft.	24.10	31.95		
	4.2	C = ===	250.20	222.45		
	1:3	Sq.m. Sq.ft.	259.30 24.10	333.15 30.95		
		oq.it.	24.10	30.33		
	) Extra for mixing pigment of required colour	Sq.m.	1.90	15.40		
		Sq.ft.	0.20	1.45		
		•	40.50	40.50		
f	Extra for first floor	Sq.m.	49.50 4.60	49.50 4.60		
		Sq.ft.	4.60	4.60		
9	) Extra for every additional floor above first floor.	Sq.m.	39.60	39.60		
		Sq.ft.	3.70	3.70		
		_				
15-39	Extra for ceiling plaster of any description in any floor for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) height	•	56.10	70.90		
	(1.5m) neight or part thereof beyond 15 ft (4.5m) neight	Sq.ft.	5.20	6.60		
15-40	Extra for wall plaster or pointing of any description in any floor for	Sq.m.	41.05	47.25		
15-40	every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) height	Sq.ft.	3.80	4.40		
	γ το τη ( το τη το τις το	94	0.00			
15-41	Petty repairs, after removing the loose matter, to fire places, ceiling,	Sq.m.	135.80	278.35		
10 11	soffits, walls, columns, beams and verandah including preparing	Sq.ft.	12.60	25.85		
	surface and curing.	'				
15-42	Removing mud plaster & disposing of the rubbish.					
i	From walls	Sq.m.	19.80	20.80		
		Sq.ft.	1.85	1.95		
	Farm and	0	44.05	45.00		
i	From roof	Sq.m. Sq.ft.	14.85 1.40	15.60 1.45		
		5q.it.	1.40	1.40		
15-43	Removing cement or lime plaster of any thickness from ceiling and	Sq.m.	43.50	50.35		
	disposing of the rubbish in any floor	Sq.ft.	4.05	4.70		
15-44	Plastering in patches in cement sand mortar 1:4 including curing and				15.1	
	scraping old damaged portions in regular shape and removal of					
	rubbish from the site in ground floor					
	) 3/8 inch (9 mm) thick plastering	Sq.m.	157.10	251.05		
		Sq.ft.	14.60	23.35		
L			<u> </u>	<u> </u>	L	

Sr. No.	Description	l lmi4	Rate (Rs.)		Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
b)	1/2" (13 mm) thick	Sq.m.	168.20	297.80	
D)	1/2 (13 Hill) trick	Sq.m. Sq.ft.	15.65	297.00	
		Oq.ii.	10.00	27.70	
c)	3/4" (19 mm) thick	Sq.m.	180.85	371.45	
		Sq.ft.	16.80	34.50	
d)	1" (25 mm) thick	Sq.m.	218.25	472.25	
	(*) [S37]	Sq.ft.	20.30	43.90	
e)	Extra for patch plaster and finishing of any description on external face item.	Sq.m.	30.65	32.15 3.00	
	lace item.	Sq.ft.	2.85	3.00	
f)	Extra for patch plaster and finishing of any description in basement	Sq.m.	19.80	19.80	
	and first floor.	Sq.ft.	1.85	1.85	
a)	Extra for patch plaster and finishing of any description in every addition	Sq.m.	14.85	14.85	
g)	Extra for pater plaster and impaining or any accompliant in every accuracy	Sq.ff.	1.40	1.40	
15-45	Scraping, rubbing and cleaning of oil bound distemper from ceiling and	Sq.m.	28.45	47.20	15.5.2
	walls including removal of rubbish in all floor items.	Sq.ft.	2.65	4.40	
15-46	Scraping, rubbing and cleaning emulsion finish distemper, snowcem	Sq.m.	48.25	59.30	15.5.2
	from walls and ceiling including removal of rubbish in all floor items.	Sq.ft.	4.50	5.50	
15-47	Brushing and cleaning with solution of caustic soda the surface of	Sq.m.	27.85	38.85	
	stone masonry, brick masonry and concrete including removal of	Sq.ft.	2.60	3.60	
	rubbish in all floor items.				
15-48	White washing on old surface of walls & ceiling including dusting and				15.3
10 40	cleaning in basement and ground floor				13.3
a)	One coat	Sq.m.	19.80	22.90	
		Sq.ft.	1.85	2.15	
b)	Two coats	Sq.m. Sq.ft.	24.75 2.30	29.10 2.70	
		oq.ii.	2.50	2.70	
c)	Three coats	Sq.m.	29.70	35.35	
		Sq.ft.	2.75	3.30	
15-49	Colour washing on old surface of walls and ceiling including dusting				15.4
	and cleaning in basement and ground floor				
a)	One coat	Sq.m.	20.80	24.25	
a)	5110 50at	Sq.m. Sq.ft.	1.95	2.25	
b)	Two coats	Sq.m.	25.75	30.65	
		Sq.ft.	2.40	2.85	
c)	Three coats	Sq.m.	30.70	37.05	
ĺ		Sq.ft.	2.85	3.45	

S: No		Description	l lmi4	Rat	te (Rs.)	Ref. Tech.	
Sr. No.	•	Description	Unit	Labour	Composite	Specs.	
15-50		Chalk washing on old surface of walls and ceiling including dusting and				15.3	
		cleaning in basement and ground floor				10.0	
	a)	One coat	Sq.m.	9.90	12.55		
			Sq.ft.	0.90	1.15		
	b)	Two coats	Sq.m.	14.85	17.85		
		(*) [27]	Sq.ft.	1.40	1.65		
	c)	Three coats	Sq.m.	19.80	23.65		
			Sq.ft.	1.85	2.20		
15-51		Cement washing on old surface of walls and ceiling including dusting				15.3.5	
	a)	and cleaning in basement and ground floor	Sq.m.	9.90	13.35		
	u)	Cho ddat	Sq.ft.	0.90	1.25		
	b)	Two coats	Sq.m.	14.85	20.45		
	~,		Sq.ft.	1.40	1.90		
	c)	Three coats	Sq.m.	19.80	26.20		
	,		Sq.ft.	1.85	2.45		
15-52		Painting with snowcem or similar make and quality on old surface of				15.5	
		walls and ceiling including dusting and cleaning in basement and ground floor					
	a)	One coat	Sq.m.	47.50	81.90		
	ω,		Sq.ft.	4.40	7.60		
	b)	Two coats	Sq.m.	57.00	107.45		
	- /		Sq.ft.	5.30	10.00		
15-53		Oil free distempering of approved make and shade on old surface of				15.5	
		walls and ceiling including dusting, sand papering and cleaning in					
	a)	basement and ground floor. One coat	Sq.m.	23.75	39.35		
	ω,		Sq.ft.	2.20	3.65		
	b)	Two coats	Sq.m.	38.00	59.90		
	,		Sq.ft.	3.55	5.55		
	c)	Three coats	Sq.m.	47.50	69.85		
			Sq.ft.	4.40	6.50		
15-54		Distempering with Berger/ ICI or equivalent synthetic vinyl emulsion				15.7	
		paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning in basement and ground floor.					
	a)	One coat	Sq.m.	33.90	149.30		
	a)	One coat	Sq.m. Sq.ft.	3.15	13.90		
	b)	Two coats	Sq.m.	47.50	194.45		
	~,		Sq.ft.	4.40	18.05		
	c)	Three coats	Sq.m.	57.00	219.00		
	1		Sq.ft.	5.30	20.35		
L							

			Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Unit	Labour	Composite	Specs.
				Compound	
15-55	Applying weather resistant paint coating such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.				15.7
a)	One coat	Sq.m.	92.30	300.20	
b)	Two coats	Sq.ft. Sq.m.	8.60 103.15	27.90 370.45	
	TWO GOLDS	Sq.ft.	9.60	34.45	
c)	Three coats	Sq.m. Sq.ft.	130.30 12.10	438.45 40.75	
15-56	White washing three coats including dusting, filling the holes, cracks and removing inequalities, if any, at any height in any floor.	Sq.m. Sq.ft.	25.60 2.40	55.00 5.10	15.3
15-57	Colour washing two coats over and including the cost of one priming coat of lie wash including dusting, filling the holes, cracks and removing inequalities, if any, at any height in any floor	Sq.m. Sq.ft.	28.20 2.60	60.50 5.60	15.4
15-58	Chalk washing three coats at any height in any floor.	Sq.m. Sq.ft.	26.05 2.40	35.30 3.30	
15-59	Cement washing two coats at any height in any floor.	Sq.m. Sq.ft.	15.70 1.45	59.65 5.55	15.3.5
15-60	Oil free distempering of approved make and shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sand papering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor.	Sq.m. Sq.ft.	70.80 6.60	102.85 9.55	15.5
15-61	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sand papering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor.		85.05 7.90	274.00 25.45	15.5
15-62	Snow ceming of approved make and shade in two coats well scrubbed into the surface including finishing smooth at any height in ground floor and basement		80.30 7.45	137.15 12.75	
15-63	Applying weather resistant paint coating such as ICI weather shield, Berger weather coat or equivalent to interior or exterior walls or ceiling including supplying all labour, materials, scaffoldings and removal of debris etc.		114.00 10.60	444.05 41.25	15.7
15-64	Extra for making band of required size in white wash, colour wash and distemper at any height in ground floor and basement	Sq.m. Sq.ft.	81.05 7.55	154.73 14.40	
15-65	Applying architectural coating such as Rockwall, Durock, Graphito or equivalent to interior or exterior walls including supplying all labour, materials, scaffoldings and removal of debris etc.	Sq.m. Sq.ft.	114.00 10.60	256.80 23.85	15.8

C: No	Description	Unit	Rat	e (Rs.)	Ref. Tech.
Sr. No.	Description	Onit	Labour	Composite	Specs.
15-66	Supply and fixing of National tiles facing strips/chequered tiles on the plastered surface on exterior faces of building including labour, scaffoldings and removal of debris etc.				14.4
a)	Glazed strip tiles	Sq.m.	278.45	1,410.95	
		Sq.ft.	25.90	131.15	
b) c)	Unglazed strip tiles  Rough glazed strip tiles  Extra over respective payable items of ground floor	Sq.m. Sq.ft. Sq.m. Sq.ft.	278.45 25.90 278.45 25.90	1,268.50 117.90 1,339.75 124.50	
a)	For first floor	%	0.10	0.10	
		Increase	*****		
b)	For every additional floor above first floor	% Increase	0.08	0.08	