

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
12-1	Providing, dressing and laying dry uncoursed rubble masonry in retaining or compound walls including scaffolding.	Cu.m.	1,750.70	4,153.30	12.2.1
		Cu.ft.	49.60	117.60	
12-2	Providing, dressing and laying dry coursed rubble masonry in retaining or compound walls including scaffolding.	Cu.m.	2,497.95	4,867.65	12.2.4
		Cu.ft.	70.75	137.85	
12-3	Providing, dressing and laying dry coursed or uncoursed rubble pitching of any thickness	Cu.m.	2,060.30	4,216.30	12.2.4
		Cu.ft.	58.35	119.40	
12-4	Providing, dressing and laying uncoursed rubble masonry in foundation, plinth and basement including scaffolding and curing.				12.2.1
a)	In mud mortar	Cu.m.	1,915.40	3,915.05	12.2.1
		Cu.ft.	54.25	110.90	
b)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m.	2,671.80	8,437.50	
		Cu.ft.	75.65	238.95	
	1 : 4	Cu.m.	2,671.80	7,821.85	
		Cu.ft.	75.65	221.50	
	1 : 6	Cu.m.	2,671.80	7,201.50	
		Cu.ft.	75.65	203.95	
	1 : 8	Cu.m.	2,671.80	6,878.95	
		Cu.ft.	75.65	194.80	
12-5	Providing, dressing and laying coursed rubble masonry in foundation, plinth and basement including scaffolding and curing.				12.2.3
a)	In mud mortar	Cu.m.	2,920.40	3,472.10	
		Cu.ft.	82.70	98.35	
b)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m.	3,530.40	7,128.00	
		Cu.ft.	100.00	201.85	
	1 : 4	Cu.m.	3,530.40	6,720.00	
		Cu.ft.	100.00	190.30	
	1 : 6	Cu.m.	3,530.40	6,190.40	
		Cu.ft.	100.00	175.30	
	1 : 8	Cu.m.	3,530.40	5,953.35	
		Cu.ft.	100.00	168.60	
12-6	Providing, dressing and laying random rubble stone masonry in foundation, plinth and basement including scaffolding and curing.				12.2
a)	In mud mortar	Cu.m.	2,554.40	5,001.90	
		Cu.ft.	72.40	141.78	
b)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m.	3,030.20	8,719.80	
		Cu.ft.	85.80	246.95	
	1 : 4	Cu.m.	3,030.20	8,206.60	
		Cu.ft.	85.80	232.40	

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.				
			Labour	Composite					
12-7	Providing dressing and laying Ashlar Fine masonry in foundation, plinth and basement including scaffolding and curing. a) In Cement, lawrencepur sand mortar	1 : 6	Cu.m.	3,030.20	7,644.90	12.3			
			Cu.ft.	85.80	216.50				
		1 : 8	Cu.m.	3,030.20	7,364.05				
			Cu.ft.	85.80	208.55				
		1 : 3	Cu.m.	8,851.90	19,451.00				
			Cu.ft.	250.70	550.85				
		1 : 4	Cu.m.	8,851.90	19,210.25				
			Cu.ft.	250.70	544.05				
		1 : 6	Cu.m.	8,851.90	18,209.95				
			Cu.ft.	250.70	515.70				
		12-8	Providing dressing and laying Ashlar rough tooled or blocks in course masonry in foundation, plinth and basement including scaffolding and curing. a) In cement, sand mortar	1 : 3	Cu.m.		8,356.58	14,328.75	12.3
					Cu.ft.		236.65	405.80	
1 : 4	Cu.m.			8,356.58	13,959.65				
	Cu.ft.			236.65	395.35				
1 : 6	Cu.m.			8,356.58	11,917.85				
	Cu.ft.			236.65	337.50				
12-9	Providing dressing and laying Ashlar rock rustic or quarry faced masonry in foundation, plinth and basement including scaffolding and curing. a) In Cement, lawrencepur sand mortar	1 : 3	Cu.m.	7,914.00	13,109.19	12.3			
			Cu.ft.	224.15	371.25				
		1 : 4	Cu.m.	7,914.00	12,542.87				
			Cu.ft.	224.15	355.20				
		1 : 6	Cu.m.	7,914.00	11,983.81				
			Cu.ft.	224.15	339.40				

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
12-10	Providing dressing and laying Ashlar chamferred masonry in foundation, plinth and basement including scaffolding and curing.				
a)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	8,264.42 234.05	15,842.75 448.70	
	1 : 4	Cu.m. Cu.ft.	8,264.42 234.05	15,522.10 439.60	
	1 : 6	Cu.m. Cu.ft.	8,264.42 234.05	15,153.00 429.15	
12-11	Providing dressing and laying Ashlar fine stone masonry in plain or chequerred tread or risers of steps in course masonry in foundation, plinth basement & ground floor, including scaffolding and curing.				12.3
a)	In cement, sand mortar 1 : 3	Cu.m. Cu.ft.	10,971.73 310.75	21,343.15 604.45	
	1 : 4	Cu.m. Cu.ft.	10,971.73 310.75	20,290.82 574.65	
	1 : 6	Cu.m. Cu.ft.	10,971.73 310.75	19,406.23 549.60	
12-12	Providing, dressing and laying uncoursed rubble masonry in superstructure including scaffolding and curing in ground floor.				12.2.2
a)	In mud mortar	Cu.m. Cu.ft.	2,176.20 61.65	5,811.15 164.60	
b)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	2,729.75 77.30	8,676.21 245.70	
	1 : 4	Cu.m. Cu.ft.	2,729.75 77.30	8,031.28 227.45	
	1 : 6	Cu.m. Cu.ft.	2,729.75 77.30	7,395.47 209.45	
	1 : 8	Cu.m. Cu.ft.	2,729.75 77.30	7,324.33 207.45	
12-13	Providing, dressing and laying coursed rubble masonry in superstructure including scaffolding and curing in ground floor (steel reinforcement if used will be paid separately)				12.2.3
a)	In mud mortar	Cu.m. Cu.ft.	3,605.85 102.10	4,252.10 120.40	
b)	In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	3,819.35 108.15	7,068.83 200.20	
	1 : 4	Cu.m. Cu.ft.	3,819.35 108.15	6,356.06 180.00	
	1 : 6	Cu.m. Cu.ft.	3,819.35 108.15	5,574.12 157.85	

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.	
			Labour	Composite		
12-14	1 : 8	Cu.m. Cu.ft.	3,819.35 108.15	5,440.22 154.05	12.2.2	
	Providing, dressing and laying random rubble stone masonry in superstructure including scaffolding and curing in ground floor.					
	a) In mud mortar	Cu.m. Cu.ft.	4,081.65 115.60	7,339.50 207.85		
	b) In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	3,811.10 107.95	9,075.89 257.05		
	1 : 4	Cu.m. Cu.ft.	3,811.10 107.95	8,551.55 242.20		
	1 : 6	Cu.m. Cu.ft.	3,811.10 107.95	7,968.47 225.65		
	1 : 8	Cu.m. Cu.ft.	3,811.10 107.95	7,646.61 216.55		
	12-15	Providing, dressing and laying ashlar fine masonry in superstructure including scaffolding and curing in ground floor.				12.3
	a) In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	10,670.25 302.20	20,201.36 572.10		
	1 : 4	Cu.m. Cu.ft.	10,670.25 302.20	19,794.37 560.60		
1 : 6	Cu.m. Cu.ft.	10,670.25 302.20	18,777.41 531.80			
12-16	Providing, dressing and laying ashlar rough tooled or blocks in course masonry in superstructure including scaffolding and curing in ground floor.			12.3		
a) In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	7,008.22 198.50	14,801.45 419.20			
1 : 4	Cu.m. Cu.ft.	7,008.22 198.50	14,408.92 408.05			
1 : 6	Cu.m. Cu.ft.	7,008.22 198.50	12,450.04 352.60			
12-17	Providing, dressing and laying ashlar rock rustic or guary faced masonry in superstructure including scaffolding and curing in ground floor.			12.3		
a) In Cement, lawrencepur sand mortar 1 : 3	Cu.m. Cu.ft.	6,709.40 190.00	14,662.89 415.25			
1 : 4	Cu.m. Cu.ft.	6,709.40 190.00	14,036.01 397.50			
1 : 6	Cu.m. Cu.ft.	6,709.40 190.00	13,405.07 379.65			

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
12-18	Providing, dressing and laying ashlar fine chamfered masonry in superstructure including scaffolding and curing in ground floor. a) In Cement, lawrencepur sand mortar 1 : 3 1 : 4 1 : 6	Cu.m. Cu.ft.	9,212.02	18,744.94	12.3
			260.90	530.85	
		Cu.m. Cu.ft.	9,212.02	18,733.79	
			260.90	530.55	
		Cu.m. Cu.ft.	9,212.02	17,934.21	
			260.90	507.90	
12-19	Providing, dressing and laying ashlar fine stone masonry punched work in superstructure including scaffolding and curing in ground floor. (Gross measurement will be made). a) In cement, sand mortar 1 : 3 1 : 4 1 : 6	Cu.m. Cu.ft.	10,070.73	22,978.41	12.3
			285.20	650.75	
		Cu.m. Cu.ft.	10,070.73	21,770.00	
			285.20	616.55	
		Cu.m. Cu.ft.	10,070.73	21,374.83	
			285.20	605.35	
12-20	Providing, dressing and laying ashlar fine stone masonry in sink or moulded work upto & sectional area of 50 Sq.in. (325 Sq.cm) in cornice, coping and architrave etc. in superstructure including scaffolding and curing in ground floor. a) In Cement, lawrencepur sand mortar 1 : 3 1 : 4 1 : 6	R.M. R.ft.	407.41	783.35	12.5
			124.20	238.75	
		R.M. R.ft.	407.41	751.40	
			124.20	229.05	
		R.M. R.ft.	407.41	748.65	
			124.20	228.20	
12-21	Providing, dressing and laying ashlar fine stone masonry in sink or moulded work above sectional area of 50 sq.in. to 100 sq.in. (325 sq.cm to 650 sq.cm) in cornice, coping and architrave etc. in superstructure including scaffolding and curing in ground floor. a) In Cement, lawrencepur sand mortar 1 : 3 1 : 4 1 : 6	R.M. R.ft.	837.55	1,577.75	12.5
			255.30	480.90	
		R.M. R.ft.	837.55	1,512.95	
			255.30	461.15	
		R.M. R.ft.	837.55	1,507.50	
			255.30	459.50	
12-22	Dressing stones (Dressed face shall be considered for measurement). a) Random rubble hammer dressed	Sq.m.	664.40	720.70	12.2
		Sq.ft.	61.75	67.00	

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
b)	Ashlar rough tool dressed	Sq.m.	1,127.90	1,181.85	12.1
		Sq.ft.	104.80	109.85	
c)	Ashlar chisel dressed	Sq.m.	1,289.60	1,360.65	
		Sq.ft.	119.85	126.45	
d)	Ashlar fine dressed	Sq.m.	1,455.55	1,498.00	
		Sq.ft.	135.25	139.20	
12-23	Extra for providing, dressing and laying stone masonry for arches of any kind of walls including scaffolding, formwork and its removal, raking out joints and curing.	Cu.m.	829.60	1,374.20	
		Cu.ft.	23.50	38.90	
12-24 a)	Extra for first floor over item No.12 - 12 to 12 - 14	Cu.m.	716.75	752.60	
		Cu.ft.	20.30	21.30	
b)	Extra for every additional floor above first floor on item 12 - 24 (a)	Cu.m.	522.15	548.25	
		Cu.ft.	14.80	15.55	
12-25 a)	Extra for first floor over item No.12 - 15 to 12 - 18.	Cu.m.	892.45	937.05	
		Cu.ft.	25.25	26.55	
b)	Extra for every additional floor above first floor on item 12 - 25 (a)	Cu.m.	533.75	560.45	
		Cu.ft.	15.10	15.85	
12-26 a)	Extra for punched work in first floor on item No.12 - 19.	Cu.m.	771.65	810.25	
		Cu.ft.	21.85	22.95	
b)	Extra for every additional floor above first floor on item 12 - 26 (a).	Cu.m.	539.25	566.20	
		Cu.ft.	15.25	16.05	
12-27 a)	Extra for first floor on item 12 - 20.	R.M.	8.20	8.60	
		R.ft.	2.50	2.60	
b)	Extra for every additional floor above first floor on item 12 - 27 (a).	R.M.	5.95	6.25	
		R.ft.	1.80	1.90	
12-28 a)	Extra for first floor on item 12 - 21.	R.M.	18.90	19.85	
		R.ft.	5.75	6.05	
b)	Extra for every additional floor above first floor on item 12 - 28 (a).	R.M.	12.15	12.75	
		R.ft.	3.70	3.90	
12-29	Extra for stone masonry of any description in any floor or other than building for every 5 ft. (1.5 m.) height or part thereof beyond 15ft. (4.5m) height.	Cu.m.		386.80	
		Cu.ft.		10.95	
12-30	Extra for stone masonry in cornice, coping and architrave in any floor or other than building for every 5 ft.(1.5m) height or part thereof beyond 15ft. (4.5m) on item 12-21	R.M.	6.40	6.70	
		R.ft.	1.95	2.05	
12-31	Extra for stone masonry in cornice, coping and architrave in any floor or other than building for every 5 ft. (1.5m) height or part thereof beyond 15ft. (4.5m) on item 12-22	R.M.	9.45	9.90	
		R.ft.	2.90	3.00	
12-32	Providing and laying of PVC pipe 4" dia (Medium class) in stone masonry wall for weepholes, complete in all respects.	R.M.	9.00	552.75	
		R.ft.	2.74	168.52	

Sr.No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
12-33	Providing, dressing and laying coursed rubble masonry in foundation, plinth and basement including scaffolding and curing.				
a)	In mud mortar	Cu.m. Cu.ft.	2920.40 82.78	3472.10 98.42	
b)	in cement , local and mortar				
	1 : 3	Cu.m. Cu.ft.	3530.40 100.07	5843.48 165.63	
	1 : 4	Cu.m. Cu.ft.	3530.40 100.07	5513.47 156.28	
	1 : 6	Cu.m. Cu.ft.	3530.40 100.07	5253.13 148.90	
	1 : 8	Cu.m. Cu.ft.	3530.40 100.07	4837.14 137.11	

