

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1994.70 56.50	4407.15 124.80
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1994.70 56.50	4335.45 122.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1994.70 56.50	4292.35 121.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1994.70 56.50	4262.50 120.70
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1386.05 39.25	3233.20 91.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1386.05 39.25	3170.50 89.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1386.05 39.25	3134.60 88.75
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1386.05 39.25	3109.00 88.05
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1408.80 39.90	3632.95 102.90
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1408.80 39.90	3559.95 100.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1408.80 39.90	3518.15 99.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1408.80 39.90	3487.00 98.75
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1126.00 31.90	3126.75 88.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1126.00 31.90	3033.30 85.90
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1126.00 31.90	2978.30 84.35
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1126.00 31.90	2939.85 83.25

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1994.70 56.50	4968.70 140.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1994.70 56.50	4822.80 136.60
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1994.70 56.50	4751.05 134.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1994.70 56.50	4708.00 133.35
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1994.70 56.50	4678.10 132.50
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1386.05 39.25	3669.40 103.90
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1386.05 39.25	3545.20 100.40
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1386.05 39.25	3482.50 98.65
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1386.05 39.25	3446.65 97.60
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1386.05 39.25	3419.80 96.85
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1408.80 39.90	4156.70 117.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1408.80 39.90	4012.00 113.60
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1408.80 39.90	3939.05 111.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1408.80 39.90	3895.95 110.35
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1408.80 39.90	3866.10 109.50
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1126.00 31.90	3625.70 102.70
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1126.00 31.90	3438.80 97.40

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1126.00	3345.35
		Cu.ft.	31.90	94.75
iv)	Cement sand mortar 1 : 5	Cu.m.	1126.00	3290.30
		Cu.ft.	31.90	93.20
v)	Cement sand mortar 1 : 6	Cu.m.	1126.00	3250.65
		Cu.ft.	31.90	92.05
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2217.70	4610.70
		Cu.ft.	62.80	130.60
ii)	Cement sand mortar 1 : 4	Cu.m.	2217.70	4538.95
		Cu.ft.	62.80	128.55
iii)	Cement sand mortar 1 : 5	Cu.m.	2217.70	4495.90
		Cu.ft.	62.80	127.35
iv)	Cement sand mortar 1 : 6	Cu.m.	2217.70	4466.00
		Cu.ft.	62.80	126.50
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1609.05	3442.80
		Cu.ft.	45.55	97.50
ii)	Cement sand mortar 1 : 4	Cu.m.	1609.05	3380.10
		Cu.ft.	45.55	95.75
iii)	Cement sand mortar 1 : 5	Cu.m.	1609.05	3344.25
		Cu.ft.	45.55	94.70
iv)	Cement sand mortar 1 : 6	Cu.m.	1609.05	3318.60
		Cu.ft.	45.55	94.00
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1617.80	3826.10
		Cu.ft.	45.80	108.35
ii)	Cement sand mortar 1 : 4	Cu.m.	1617.80	3753.15
		Cu.ft.	45.80	106.30
iii)	Cement sand mortar 1 : 5	Cu.m.	1617.80	3711.30
		Cu.ft.	45.80	105.10
iv)	Cement sand mortar 1 : 6	Cu.m.	1617.80	3681.40
		Cu.ft.	45.80	104.25

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-4	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1126.00 31.90	3110.90 88.10
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1126.00 31.90	3017.45 85.45
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1126.00 31.90	2963.65 83.95
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1126.00 31.90	2925.20 82.85
	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2217.70 62.80	5169.80 146.40
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2217.70 62.80	5025.10 142.30
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2217.70 62.80	4952.15 140.25
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2217.70 62.80	4910.30 139.05
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2217.70 62.80	4880.40 138.20
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1609.05 45.55	3876.60 109.80
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1609.05 45.55	3752.40 106.25
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1609.05 45.55	3690.90 104.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1609.05 45.55	3655.05 103.50
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1609.05 45.55	3628.20 102.75
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1126.00 31.90	3850.70 109.05
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1126.00 31.90	3706.05 104.95
iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1126.00 31.90	3633.05 102.90	

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1126.00	3591.20
		Cu.ft.	31.90	101.70
v)	Cement sand mortar 1 : 6	Cu.m.	1126.00	3561.35
		Cu.ft.	31.90	100.85
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1126.00	3607.40
		Cu.ft.	31.90	102.15
ii)	Cement sand mortar 1 : 3	Cu.m.	1126.00	3421.70
		Cu.ft.	31.90	96.90
iii)	Cement sand mortar 1 : 4	Cu.m.	1126.00	3328.25
		Cu.ft.	31.90	94.25
iv)	Cement sand mortar 1 : 5	Cu.m.	1126.00	3274.45
		Cu.ft.	31.90	92.75
v)	Cement sand mortar 1 : 6	Cu.m.	1126.00	3234.80
		Cu.ft.	31.90	91.60
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	338.05	338.05
		Cu.ft.	9.55	9.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	268.40	268.40
		Cu.ft.	7.60	7.60
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80