


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4401.85 124.65
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4325.85 122.50
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4282.45 121.30
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4250.20 120.35
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3491.30 98.90
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3427.55 97.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3389.10 96.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3362.55 95.25
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3713.45 105.15
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3637.80 103.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3594.40 101.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3562.20 100.90
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3212.35 91.00
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3115.50 88.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	3058.45 86.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	3018.60 85.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1799.65 50.95	4977.05 140.95
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4825.80 136.65
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4751.40 134.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4706.80 133.30
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4675.80 132.40
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1498.20 42.45	3939.85 111.60
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3809.85 107.90
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3744.85 106.05
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3707.65 105.00
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3681.10 104.25
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1315.45 37.25	4250.45 120.40
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	4100.40 116.15
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	4024.80 114.00
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3980.20 112.70
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3949.20 111.85
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3724.70 105.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3530.90 100.00

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3434.05
		Cu.ft.	30.20	97.25
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3377.05
		Cu.ft.	30.20	95.65
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3335.95
		Cu.ft.	30.20	94.50
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2054.15	4637.65
		Cu.ft.	58.15	131.35
ii)	Cement sand mortar 1 : 4	Cu.m.	2054.15	4562.00
		Cu.ft.	58.15	129.20
iii)	Cement sand mortar 1 : 5	Cu.m.	2054.15	4518.60
		Cu.ft.	58.15	127.95
iv)	Cement sand mortar 1 : 6	Cu.m.	2054.15	4486.40
		Cu.ft.	58.15	127.05
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1752.70	3731.15
		Cu.ft.	49.65	105.65
ii)	Cement sand mortar 1 : 4	Cu.m.	1752.70	3667.35
		Cu.ft.	49.65	103.85
iii)	Cement sand mortar 1 : 5	Cu.m.	1752.70	3628.95
		Cu.ft.	49.65	102.75
iv)	Cement sand mortar 1 : 6	Cu.m.	1752.70	3602.40
		Cu.ft.	49.65	102.00
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1552.75	3934.90
		Cu.ft.	43.95	111.45
ii)	Cement sand mortar 1 : 4	Cu.m.	1552.75	3859.25
		Cu.ft.	43.95	109.30
iii)	Cement sand mortar 1 : 5	Cu.m.	1552.75	3815.85
		Cu.ft.	43.95	108.05
iv)	Cement sand mortar 1 : 6	Cu.m.	1552.75	3784.85
		Cu.ft.	43.95	107.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d)	12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3196.50 90.55
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3099.65 87.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	3043.85 86.20
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	3002.75 85.05
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a)	4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2054.15 58.15	5209.55 147.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2054.15 58.15	5059.55 143.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2054.15 58.15	4983.90 141.15
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2054.15 58.15	4940.50 139.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2054.15 58.15	4909.50 139.05
b)	6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1752.70 49.65	4177.25 118.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1752.70 49.65	4048.50 114.65
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1752.70 49.65	3983.50 112.80
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1752.70 49.65	3946.30 111.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1752.70 49.65	3919.70 111.00
c)	8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3978.80 112.70
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3828.80 108.45
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3753.15 106.30



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3709.75
		Cu.ft.	30.20	105.05
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3678.75
		Cu.ft.	30.20	104.20
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1066.95	3706.40
		Cu.ft.	30.20	104.95
ii)	Cement sand mortar 1 : 3	Cu.m.	1066.95	3513.85
		Cu.ft.	30.20	99.50
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3416.95
		Cu.ft.	30.20	96.75
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3359.95
		Cu.ft.	30.20	95.15
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3320.10
		Cu.ft.	30.20	94.05
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	373.25	373.25
		Cu.ft.	10.55	10.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	303.60	303.60
		Cu.ft.	8.60	8.60
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80