


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4272.80 121.00
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4201.20 119.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4158.70 117.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4129.25 116.95
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3394.40 96.15
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3332.60 94.40
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3297.25 93.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3272.00 92.65
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3596.15 101.85
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3524.25 99.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3481.75 98.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3452.30 97.75
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3114.25 88.20
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3022.10 85.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2967.85 84.05
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2928.75 82.95

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m.	1799.65	4820.30
		Cu.ft.	50.95	136.50
ii)	Cement sand mortar 1 : 3	Cu.m.	1799.65	4677.65
		Cu.ft.	50.95	132.45
iii)	Cement sand mortar 1 : 4	Cu.m.	1799.65	4605.75
		Cu.ft.	50.95	130.45
iv)	Cement sand mortar 1 : 5	Cu.m.	1799.65	4563.25
		Cu.ft.	50.95	129.25
v)	Cement sand mortar 1 : 6	Cu.m.	1799.65	4533.80
		Cu.ft.	50.95	128.40
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m.	1498.20	3820.60
		Cu.ft.	42.45	108.20
ii)	Cement sand mortar 1 : 3	Cu.m.	1498.20	3698.15
		Cu.ft.	42.45	104.75
iii)	Cement sand mortar 1 : 4	Cu.m.	1498.20	3636.30
		Cu.ft.	42.45	103.00
iv)	Cement sand mortar 1 : 5	Cu.m.	1498.20	3600.95
		Cu.ft.	42.45	102.00
v)	Cement sand mortar 1 : 6	Cu.m.	1498.20	3574.50
		Cu.ft.	42.45	101.25
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m.	1315.45	4107.80
		Cu.ft.	37.25	116.35
ii)	Cement sand mortar 1 : 3	Cu.m.	1315.45	3963.90
		Cu.ft.	37.25	112.25
iii)	Cement sand mortar 1 : 4	Cu.m.	1315.45	3892.00
		Cu.ft.	37.25	110.20
iv)	Cement sand mortar 1 : 5	Cu.m.	1315.45	3850.75
		Cu.ft.	37.25	109.05
v)	Cement sand mortar 1 : 6	Cu.m.	1315.45	3820.05
		Cu.ft.	37.25	108.20
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m.	1066.95	3602.20
		Cu.ft.	30.20	102.00
ii)	Cement sand mortar 1 : 3	Cu.m.	1066.95	3416.70
		Cu.ft.	30.20	96.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3324.60
		Cu.ft.	30.20	94.15
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3271.55
		Cu.ft.	30.20	92.65
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3232.45
		Cu.ft.	30.20	91.55
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2054.15	4509.30
		Cu.ft.	58.15	127.70
ii)	Cement sand mortar 1 : 4	Cu.m.	2054.15	4437.35
		Cu.ft.	58.15	125.65
iii)	Cement sand mortar 1 : 5	Cu.m.	2054.15	4396.10
		Cu.ft.	58.15	124.50
iv)	Cement sand mortar 1 : 6	Cu.m.	2054.15	4365.45
		Cu.ft.	58.15	123.65
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1752.70	3634.25
		Cu.ft.	49.65	102.90
ii)	Cement sand mortar 1 : 4	Cu.m.	1752.70	3573.65
		Cu.ft.	49.65	101.20
iii)	Cement sand mortar 1 : 5	Cu.m.	1752.70	3538.30
		Cu.ft.	49.65	100.20
iv)	Cement sand mortar 1 : 6	Cu.m.	1752.70	3513.05
		Cu.ft.	49.65	99.50
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1552.75	3817.65
		Cu.ft.	43.95	108.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1552.75	3745.70
		Cu.ft.	43.95	106.10
iii)	Cement sand mortar 1 : 5	Cu.m.	1552.75	3704.45
		Cu.ft.	43.95	104.90
iv)	Cement sand mortar 1 : 6	Cu.m.	1552.75	3675.00
		Cu.ft.	43.95	104.10

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3098.35 87.75
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3006.25 85.15
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2953.20 83.65
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2915.30 82.55
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2054.15 58.15	5054.05 143.15
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2054.15 58.15	4911.40 139.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2054.15 58.15	4839.50 137.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2054.15 58.15	4798.25 135.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2054.15 58.15	4768.75 135.05
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1752.70 49.65	4059.20 114.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1752.70 49.65	3936.75 111.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1752.70 49.65	3874.95 109.75
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1752.70 49.65	3839.60 108.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1752.70 49.65	3814.30 108.00
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3836.15 108.65
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3693.50 104.60
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3621.60 102.55



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3580.35
		Cu.ft.	30.20	101.40
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3550.85
		Cu.ft.	30.20	100.55
				
d) 12" (300 mm) thick hollow block masonry i)	Cement sand mortar 1 : 2	Cu.m.	1066.95	3583.90
		Cu.ft.	30.20	101.50
ii)	Cement sand mortar 1 : 3	Cu.m.	1066.95	3400.85
		Cu.ft.	30.20	96.30
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3308.75
		Cu.ft.	30.20	93.70
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3254.45
		Cu.ft.	30.20	92.15
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3216.60
		Cu.ft.	30.20	91.10
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	373.25	373.25
		Cu.ft.	10.55	10.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	303.60	303.60
		Cu.ft.	8.60	8.60
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80