

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4239.65 120.05
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4166.50 118.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4124.75 116.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4094.95 115.95
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3366.90 95.35
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3304.40 93.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3268.60 92.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3241.85 91.80
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3562.70 100.90
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3489.95 98.85
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3448.20 97.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3417.20 96.80
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3073.45 87.05
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	2980.25 84.40
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2925.40 82.85
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2887.05 81.75




Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1799.65 50.95	4795.55 135.80
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1799.65 50.95	4650.05 131.70
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1799.65 50.95	4577.30 129.65
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1799.65 50.95	4535.55 128.45
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1799.65 50.95	4505.75 127.60
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1498.20 42.45	3799.15 107.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1498.20 42.45	3675.30 104.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1498.20 42.45	3612.80 102.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1498.20 42.45	3575.80 101.25
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1498.20 42.45	3550.25 100.55
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1315.45 37.25	4081.65 115.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1315.45 37.25	3937.35 111.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1315.45 37.25	3864.60 109.45
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1315.45 37.25	3821.65 108.25
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1315.45 37.25	3791.85 107.40
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3568.20 101.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3381.85 95.80

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3288.65
		Cu.ft.	30.20	93.15
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3233.80
		Cu.ft.	30.20	91.60
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3195.45
		Cu.ft.	30.20	90.50
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2054.15	4475.40
		Cu.ft.	58.15	126.75
ii)	Cement sand mortar 1 : 4	Cu.m.	2054.15	4403.90
		Cu.ft.	58.15	124.70
iii)	Cement sand mortar 1 : 5	Cu.m.	2054.15	4360.95
		Cu.ft.	58.15	123.50
iv)	Cement sand mortar 1 : 6	Cu.m.	2054.15	4331.15
		Cu.ft.	58.15	122.65
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1752.70	3606.75
		Cu.ft.	49.65	102.15
ii)	Cement sand mortar 1 : 4	Cu.m.	1752.70	3545.45
		Cu.ft.	49.65	100.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1752.70	3508.45
		Cu.ft.	49.65	99.35
iv)	Cement sand mortar 1 : 6	Cu.m.	1752.70	3482.90
		Cu.ft.	49.65	98.65
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1552.75	3785.40
		Cu.ft.	43.95	107.20
ii)	Cement sand mortar 1 : 4	Cu.m.	1552.75	3712.65
		Cu.ft.	43.95	105.15
iii)	Cement sand mortar 1 : 5	Cu.m.	1552.75	3670.90
		Cu.ft.	43.95	103.95
iv)	Cement sand mortar 1 : 6	Cu.m.	1552.75	3641.10
		Cu.ft.	43.95	103.10

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3058.80 86.65
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	2965.60 84.00
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1066.95 30.20	2911.95 82.45
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1066.95 30.20	2872.40 81.35
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2054.15 58.15	5029.30 142.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2054.15 58.15	4885.00 138.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2054.15 58.15	4812.25 136.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2054.15 58.15	4770.50 135.10
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2054.15 58.15	4739.50 134.25
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1752.70 49.65	4037.80 114.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1752.70 49.65	3913.95 110.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1752.70 49.65	3851.40 109.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1752.70 49.65	3815.65 108.05
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1752.70 49.65	3790.10 107.35
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1066.95 30.20	3811.20 107.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1066.95 30.20	3666.95 103.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1066.95 30.20	3594.20 101.80



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3552.45
		Cu.ft.	30.20	100.60
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3522.65
		Cu.ft.	30.20	99.75
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1066.95	3551.15
		Cu.ft.	30.20	100.55
ii)	Cement sand mortar 1 : 3	Cu.m.	1066.95	3364.75
		Cu.ft.	30.20	95.30
iii)	Cement sand mortar 1 : 4	Cu.m.	1066.95	3272.80
		Cu.ft.	30.20	92.70
iv)	Cement sand mortar 1 : 5	Cu.m.	1066.95	3217.90
		Cu.ft.	30.20	91.15
v)	Cement sand mortar 1 : 6	Cu.m.	1066.95	3179.60
		Cu.ft.	30.20	90.05
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	373.25	373.25
		Cu.ft.	10.55	10.55
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	303.60	303.60
		Cu.ft.	8.60	8.60
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80