

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
2-1	Loading or unloading into or from mobile trucks, coarse aggregate, sand, stone/ brick ballast, surkhi, ashes, kankar, brick/stone bats, coal or lime etc. lead upto 100 ft (30 m)	Cu.m.	94.80	118.50	2.1.1
		Cu.ft.	2.70	3.35	2.1.3
2-2	Loading or unloading bricks or tiles into or from mobile trucks properly laid and stacked lead upto 100 ft (30 m)	1000	671.00	832.04	2.1.1
		Nos.	19.02		2.1.3
2-3	Loading or unloading into or from mobile trucks cement in bags (inside or outside the godown) and stacking lead upto 100 ft (30 m)	100	671.00	838.75	2.1.1
		Nos.			2.1.3
2-4	Loading or unloading into or from mobile trucks empty cement bags (inside or outside the godown) and stacking lead upto 100 ft (30 m)	100			2.1.1
		Nos.	8.10	10.04	2.1.3
2-5	Loading or unloading into or from mobile trucks (inside or outside the godown) and stacking, white lime in bags lead upto 100 ft (30 m)	% Kg.	12.60	15.62	2.1.1
		Cwt.	6.40	7.95	2.1.3
2-6	Loading or unloading into or from mobile trucks structural steel, R.S joists etc. lead upto 100 ft (30 m)	Tonne	32.20	40.25	2.1.1
		Ton	32.70	40.90	2.1.3
2-7	Loading or unloading 205 litre drums fuel into or from mobile trucks, lead upto 100 ft (30 m)	Each	32.70	40.55	2.1.1
					2.1.3
2-8	Loading or unloading packages of sorts weighing upto 50 kgs.	Each	32.70	40.55	2.1.1
					2.1.3
2-9	Loading or unloading timber logs or timber for shuttering, into or from mobile trucks including stacking lead upto 100 ft (30 m)	Tonne	112.40	139.38	2.1.1
		Ton	114.20	141.60	2.1.3
2-10	Loading or unloading bhoosa into or from mobile trucks lead upto 150 ft. (45 m)	% Kg.	32.70	40.55	2.1.1
		Cwt.	16.60	20.60	2.1.3
2-11	Loading or unloading timber scrap or wooden plugs into or from mobile trucks including stacking and lead upto 100 ft (30 m)	Tonne	199.60	247.50	2.1.1
		Ton	202.80	251.50	2.1.3
2-12	Loading or unloading pitching stone or spawl from mobile trucks including clearing	Cu.m.	300.30	372.37	2.1.1
		Cu.ft..	8.50	10.55	2.1.3
2-13	Loading or unloading building stone including clearing	Cu.m.	402.60	499.22	2.1.1
		Cu.ft..	11.40	14.15	2.1.3
2-14	Unloading oils.				2.1.1
a)	Crude oil (to be pumped from tanker into tank)	1000 Litre	111.60	138.38	2.1.3
		% Gallon	50.75	62.90	
b)	Crude oil (drained by gravity)	1000 Litre	111.60	138.38	
		% Gallon	50.75	62.90	
c)	Fuel oil into empty drums including stacking upto 100 ft (30 m)	Tonne	184.50	228.78	
		Ton	187.45	232.45	
d)	Petrol (4.5 litre tin)	100 Nos.	251.60	311.98	
e)	Kerosine (18 litre tin)	100 Nos.	504.10	625.08	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
2-15	Removing and stacking lead upto 100 ft (30 m)				2.1.1 2.1.3
a)	Stone, spawl, brick bats, shingle, sand, lime, surkhi, ashes, kankar and coal etc.	Cu.m. Cu.ft..	94.80 2.70	117.55 3.35	
b)	Bricks	% Nos.	671.00	832.04	
c)	Rails, girders, pipes, cement etc.	Tonne Ton	268.40 272.70	332.82 338.15	
d)	Bailey bridges & wooden structural members	% Nos.	##### 30.30	1,336.75 37.85	
2-16	Loading into mobile trucks girders, rails, permanent way material, iron work. pipes etc including lead upto 100 ft (30 m) and stacking	Tonne Ton	255.80 259.90	319.75 324.90	2.1.1 2.1.3
2-17	Unloading from mobile trucks girders, permanent way material, iron work, pipes, etc. lead upto 100 ft (30 m) but excluding stacking.	Tonne Ton	127.50 129.55	159.38 161.95	2.1.1 2.1.3
2-18	Loading or unloading bitumen, asphalt or tar in drums, into or from mobile trucks lead upto 100 ft (30 m)	Tonne Ton	188.70 191.75	188.70 191.75	2.1.1 2.1.3
2-19	Loading bailey bridge wooden structural members including stacking lead upto 100 ft (30m)	Cu.m. Cu.ft..	134.20 3.80	167.75 4.75	2.1.1 2.1.3
2-20	Unloading bailey bridge wooden structural members excluding stacking lead upto 100 ft (30m)	% Nos.	71.30 2.00	89.13 2.50	2.1.1 2.1.3
2-21	Loading into mobile trucks, steel fabrication/bars including lead upto 100 ft (30m) and stacking inside trucks.	Tonne Ton	461.30 468.70	461.30 468.70	2.1.1 2.1.3
2-22	Unloading from mobile trucks, steel fabrication/bars including lead upto 100 ft (30m) and stacking	Tonne Ton	251.60 255.65	251.60 255.65	2.1.1 2.1.3