

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-1	Boring for tubewell in all types of soil except shingle, gravel and rock from ground bed to 100ft (30m) depth including sinking and withdrawing casing pipe & disposal of excavated material within 100ft (30m)				27.1.2
a)	3" (75 mm) inner dia.	R.M. R.ft.	57.50 17.55	246.79 75.20	
b)	4" (100 mm) inner dia.	R.M. R.ft.	77.65 23.65	528.86 161.20	
c)	5" (125 mm) inner dia.	R.M. R.ft.	139.75 42.60	813.64 248.00	
d)	6" (150 mm) inner dia.	R.M. R.ft.	209.65 63.90	1,094.57 333.65	
e)	8" (200 mm) inner dia.	R.M. R.ft.	278.85 85.00	1,379.71 420.55	
f)	10" (250 mm) inner dia.	R.M. R.ft.	348.55 106.25	1,658.32 505.45	
g)	12" (300 mm) inner dia.	R.M. R.ft.	363.08 110.65	1,946.38 593.25	
h)	15" (375 mm) inner dia.	R.M. R.ft.	540.30 164.70	2,221.92 677.25	
i)	18" (450 mm) inner dia.	R.M. R.ft.	574.77 175.20	2,440.60 743.90	
27-2	Boring for tubewell in all types of soil except shingle, gravel and rock from depth 100 ft. to 200 ft. (30m to 60m.) below ground level including sinking and withdrawing of casing pipe				27.1.2
a)	5" (125 mm) inner dia.	R.M. R.ft.	237.60 72.40	1,106.56 337.30	
b)	6" (150 mm) inner dia.	R.M. R.ft.	335.44 102.25	1,368.20 417.05	
c)	8" (200 mm) inner dia.	R.M. R.ft.	362.50 110.50	1,630.55 497.00	
d)	10" (250 mm) inner dia.	R.M. R.ft.	412.07 125.60	1,895.24 577.70	
e)	12" (300 mm) inner dia.	R.M. R.ft.	448.98 136.85	2,162.66 659.20	
f)	15" (375 mm) inner dia.	R.M. R.ft.	637.28 194.25	2,421.99 738.25	
g)	18" (450 mm) inner dia.	R.M. R.ft.	667.68 203.50	2,673.05 814.75	



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-3	Boring for tubewell in all types of soil except shingle, gravel and rock from depth 200 ft. to 300 ft. (60m to 90m.) below ground level including sinking and withdrawing of casing pipe				27.1.2
a)	5" (125 mm) inner dia.	R.M. R.ft.	332.38 101.30	1,548.03 471.85	
b)	6" (150 mm) inner dia.	R.M. R.ft.	430.05 131.10	1,742.50 531.10	
c)	8" (200 mm) inner dia.	R.M. R.ft.	453.15 138.10	2,058.79 627.55	
d)	10" (250 mm) inner dia.	R.M. R.ft.	509.79 155.40	2,356.79 718.35	
e)	12" (300 mm) inner dia.	R.M. R.ft.	538.75 164.20	2,595.20 791.05	
f)	15" (375 mm) inner dia.	R.M. R.ft.	701.00 213.65	2,664.20 812.05	
g)	18" (450 mm) inner dia.	R.M. R.ft.	734.45 223.85	2,940.35 896.25	
27-4	Boring for tubewell in all types of soil except shingle, gravel and rock from depth 300 ft. to 400 ft. (90m to 120m) below ground level including sinking and withdrawing of casing pipe				27.1.2
a)	8" (200 mm) inner dia.	R.M. R.ft.	543.80 165.75	2,482.96 756.80	
b)	10" (250 mm) inner dia.	R.M. R.ft.	611.75 186.45	2,814.08 857.75	
c)	12" (300 mm) inner dia.	R.M. R.ft.	641.10 195.40	3,083.42 939.85	
d)	15" (375 mm) inner dia.	R.M. R.ft.	782.13 238.40	3,245.74 989.30	
e)	18" (450 mm) inner dia.	R.M. R.ft.	859.85 262.10	3,425.63 1,044.15	
27-5	Direct rotary and/or reverse rotary drilling of bore in all types of soil except shingle, gravel and rock.				27.1.2
a)	From ground level upto 250 ft. (75 m) below ground level				
i.	(370 mm to 450 mm) i/d (15" to 18")	R.M. R.ft.	1,185.38 361.40	1,691.99 515.85	
ii.	(500 mm to 700 mm) i/d (20" to 28")	R.M. R.ft.	1,505.43 458.97	2,095.87 638.99	
b)	Exceeding 250 ft (75 m.) depth below ground level				
i.	(375 mm to 450 mm) i/d (15" to 18")	R.M. R.ft.	1,327.62 404.76	1,889.13 575.95	
ii.	(500 mm to 750 mm) i/d (20" to 28")	R.M. R.ft.	1,671.03 509.46	2,382.34 726.32	
27-6	Direct rotary and/or reverse rotary drilling for Pilling in shingle, gravel or rock.	R.M. R.ft.	9,160.45 2,792.82	3,328.05 1,014.40	27.1.2



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-7	Direct rotary and/or reverse rotary drilling of bore in all types of soil except shingle, gravel and rock.				27.1.2
	a) From ground level upto 250 ft. (75 m) below ground level				
	i) 15" to 18" (375 mm to 450 mm) inner dia.	R.M. R.ft.	1,185.38 361.40	1,691.99 515.85	
	ii) 20" to 30" (500 mm to 750 mm) inner dia.	R.M. R.ft.	1,505.43 458.97	2,095.87 638.99	
	b) Exceeding 250 ft (75 m.) depth below ground level				
	i) 15" to 18" (375 mm to 450 mm) inner dia.	R.M. R.ft.	1,327.62 404.76	1,889.13 575.95	
	ii) 20" to 30" (500 mm to 750 mm) inner dia.	R.M. R.ft.	1,671.03 509.46	2,382.34 726.32	
27-8	Direct rotary and/or reverse rotary drilling of bore for tubewells including extraction of casing pipes in shingle, gravel and rock.				27.1.2
	a) From ground level upto 250 ft. (75 m) below ground level				
	i) 15" to 18" (375 mm to 450 mm) inner dia.	R.M. R.ft.	1,775.32 541.26	2,557.11 779.40	
	ii) 20" to 30" (500 mm to 750 mm) inner dia.	R.M. R.ft.	2,255.56 687.67	3,194.81 973.80	
	b) Exceeding 250 ft (75 m.) depth below ground level				
	i) 15" to 18" (375 mm to 450 mm) inner dia.	R.M. R.ft.	1,988.63 606.29	2,840.94 1,117.35	
	ii) 20" to 30" (500 mm to 750 mm) inner dia.	R.M. R.ft.	2,554.22 778.73	3,542.82 1,079.85	
27-9	Providing box 48"x 30"x 9" (1.2m x 0.75m x 0.23m) of deodar wood planks with compartment 4" x 4" (100mm x 100mm) including locking arrangement for preserving strata samples from borehole and painted with two coats of paint. The top and bottom of the box to be of 1/2" (12mm) planks, sides and compartments to be of 1/4" (6mm) planks.	Each	952.35	11,699.40	27.1.2.5
27-10	Furnishing sample of water from bore hole.	Per set of two bottles	158.85	207.10	27.1.2.5
27-11	Providing and installing brass strainer in tubewell bore hole including specials, sockets and studs of the nominal inner diameter.				27.1.3
	a) 2" (50 mm) dia. and 5/32" (4 mm) wall thickness	R.M. R.ft.	116.25 35.45	2,867.15 873.90	
	b) 3" (75 mm) dia. and 5/32" (4 mm) wall thickness	R.M. R.ft.	116.25 35.45	3,908.45 1,191.30	
	c) 4" (100 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	116.25 35.45	4,741.40 1,445.20	
	d) 5" (125 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	147.60 45.00	5,477.85 1,669.65	
	e) 6" (150 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	147.60 45.00	5,843.60 1,781.15	
	f) 7" (175 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	147.60 45.00	6,877.70 2,096.35	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.	
			Labour	Composite		
g)	8" (200 mm) dia. and 3/16" (5 mm) wall thickness	R.M.	213.55	8,677.75		
		R.ft.	65.10	2,645.00		
h)	9" (225 mm) dia. and 3/16" (5 mm) wall thickness	R.M.	213.55	9,227.15		
		R.ft.	65.10	2,812.45		
i)	10" (250 mm) dia. with 3/16" (5 mm) wall thickness	R.M.	213.55	10,141.33		
		R.ft.	65.10	3,091.10		
j)	10" (250 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	246.00	10,674.60		
		R.ft.	75.00	3,253.65		
k)	12" (300 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	246.00	11,672.60		
		R.ft.	75.00	3,557.85		
l)	15" (375 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	279.55	12,888.75		
		R.ft.	85.20	3,928.55		
m)	18" (450 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	279.55	17,042.40		
		R.ft.	85.20	5,194.60		
n)	20" (500 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	344.87	18,807.15		
		R.ft.	105.10	5,732.50		
o)	22" (550 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	344.87	21,634.75		
		R.ft.	105.14	6,594.35		
27-12	Providing and installing M.S. bail plug in tubewell bore hole 1.5 ft. (50cm) long and of the nominal inner diameter.					27.1.3
a)	2" (50 mm) inner dia.	Each	179.15	705.75		
b)	3" (75 mm) inner dia.	Each	179.15	998.60		
c)	4" (100 mm) inner dia.	Each	248.82	1,593.55		
d)	5" (125 mm) inner dia.	Each	248.82	2,099.20		
e)	6" (150 mm) inner dia.	Each	301.09	2,488.65		
f)	7" (175 mm) dia	Each	301.09	2,963.80		
g)	8" (200 mm) inner dia.	Each	361.92	3,205.95		
h)	9" 225 mm inner dia.	Each	361.92	3,609.50		
i)	10" (250 mm) inner dia.	Each	416.63	4,900.95		
j)	12" (300 mm) inner dia.	Each	416.63	5,923.70		
27-13	Providing and installing fibre glass strainer in tubewell bore hole including sockets and solvents.				27.1.3	
a)	8" (200 mm) dia. and 3/16" (5 mm) wall thickness	R.M.	126.35	4,301.05		
		R.ft.	38.50	1,311.00		
b)	10" (250 mm) dia. and 0.2" to 0.22" (5 mm to 5.5 mm) wall thickness	R.M.	126.35	4,861.80		
		R.ft.	38.50	1,481.90		
27-14	Providing and installing fibre glass bail/end plug in tubewell bore.				27.1.3	
a)	8" (200 mm) inner dia.	Each	36.10	511.15		
b)	10" (250 mm) inner dia.	Each	43.57	640.40		

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-15	Providing and installing fibre glass blank pipe Zamrock or similar make in tubewell bore hole including coupling and jointing with strainer.				27.1.3
a)	8" (200 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	126.35 38.50	1,304.00 397.45	
b)	10" (250 mm) dia. with 3/16" (5 mm) wall thickness	R.M. R.ft.	176.89 53.90	1,594.80 486.10	
c)	14" (350 mm) dia. and 3/16" to 1/4" (5 mm to 6 mm) wall thickness	R.M. R.ft.	235.01 71.65	1,971.65 600.95	
27-16	Providing and installing P.V.C. strainer in tubewell bore hole including sockets and solvent Shavyl Karachi or equivalent make of the nominal inner diameter.				27.1.3
a)	Class B				
i)	3" (75 mm) inner dia.	R.M. R.ft.	23.18 7.05	77.45 23.60	
ii)	4" (100 mm) inner dia.	R.M. R.ft.	23.18 7.05	100.40 30.60	
iii)	5" (125 mm) inner dia.	R.M. R.ft.	49.80 15.20	174.95 53.35	
iv)	6" (150 mm) inner dia.	R.M. R.ft.	49.80 15.20	225.20 68.65	
v)	8" (200 mm) inner dia.	R.M. R.ft.	74.00 22.55	453.05 138.10	
vi)	10" (250 mm) inner dia.	R.M. R.ft.	74.00 22.55	613.95 187.15	
vii)	12" (300 mm) inner dia.	R.M. R.ft.	108.08 32.95	704.15 214.65	
viii)	14" (350 mm) inner dia.	R.M. R.ft.	140.50 42.80	875.90 267.00	
b)	Class D				
i)	1.25" (30 mm) inner dia.	R.M. R.ft.	16.30 4.95	42.10 12.85	
ii)	1.5" (40 mm) inner dia.	R.M. R.ft.	16.30 4.95	60.15 18.35	
iii)	2" (50 mm) inner dia.	R.M. R.ft.	22.70 6.90	83.95 25.60	
iv)	3" (75 mm) inner dia.	R.M. R.ft.	32.40 9.90	112.20 34.20	
v)	4" (100 mm) inner dia.	R.M. R.ft.	48.60 14.80	144.70 44.10	
vi)	5" (125 mm) inner dia.	R.M. R.ft.	60.90 18.55	204.95 62.45	
vii)	6" (150 mm) inner dia.	R.M. R.ft.	60.90 18.55	264.85 80.75	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.	
			Labour	Composite		
27-17	Providing and installing P.V.C. elbow Shavyl or equivalent make.				27.1.3	
a)	Class B					
i)	3" (75 mm) inner dia.	Each	44.60	216.10		
ii)	4" (100 mm) inner dia.	Each	44.60	263.45		
iii)	5" (125 mm) inner dia.	Each	44.60	547.60		
iv)	6" (150 mm) inner dia.	Each	59.50	738.40		
v)	8" (200 mm) inner dia.	Each	59.50	937.75		
vi)	10" (250 mm) inner dia.	Each	59.50	1,237.15		
vii)	12" (300 mm) inner dia.	Each	89.20	1,649.65		
viii)	14" (350 mm) inner dia.	Each	89.20	2,004.85		
b)	Class D					
i)	1.25" (30 mm) inner dia.	Each	29.75	113.25		
ii)	1.5" (40 mm) inner dia.	Each	29.75	140.35		
iii)	2" (50 mm) inner dia.	Each	29.75	167.40		
iv)	3" (75 mm) inner dia.	Each	44.60	378.45		
v)	4" (100 mm) inner dia.	Each	44.60	452.90		
vi)	5" (125 mm) inner dia.	Each	44.60	550.15		
vii)	6" (150 mm) inner dia.	Each	44.60	666.65		
27-18	Providing and installing M.S. blind pipe socketed seamless welded joint or hand welded joint, M.S. reducer where necessary in tubewell bore hole including jointing and welding with strainer of the nominal inner diameter.					27.1.3
a)	2" (50 mm) dia. and 1/8" (3 mm) wall thickness	R.M. R.ft.	230.85 70.35	1,259.40 383.85		
b)	3" (75 mm) dia. and 1/8" (3 mm) wall thickness	R.M. R.ft.	230.85 70.35	1,304.25 397.55		
c)	4" (100 mm) dia. and 1/8" (3 mm) wall thickness	R.M. R.ft.	289.00 88.10	961.45 293.05		
d)	5" (125 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	289.00 88.10	1,391.00 424.00		
e)	6" (150 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	460.65 140.40	1,762.30 537.15		
f)	7" (175 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	460.65 140.40	3,087.40 941.05		
g)	8" (200 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	467.15 142.40	3,419.45 1,042.25		
h)	9" (225 mm) dia. and 3/16" (5 mm) wall thickness	R.M. R.ft.	467.15 142.40	3,846.10 1,172.30		
i)	10" (250 mm) dia. and 1/4" (6 mm) wall thickness	R.M. R.ft.	467.15 142.40	5,653.00 1,723.05		
j)	12" (300 mm) dia. and 1/4" (6 mm) wall thickness	R.M.	524.82	6,349.55		



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
		R.ft.	159.95	1,935.35	
k)	15" (375 mm) dia. and 1/4" (6 mm) wall thickness	R.M. R.ft.	524.82 159.95	7,738.74 2,358.80	
l)	18" (450 mm) dia. and 1/4" (6 mm) wall thickness	R.M. R.ft.	524.82 159.95	9,631.10 2,935.60	
m)	20" (500 mm) dia. and 1/4" (6 mm) wall thickness	R.M. R.ft.	718.05 218.85	10,524.80 3,208.00	
n)	22" (550 mm) dia. and 1/4" (6 mm) wall thickness	R.M. R.ft.	718.05 218.85	11,676.70 3,559.10	
27-19	Providing and Installing P.V.C. blind pipe Shavyl or equivalent make in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting P.V.C. pipe lines in trenches.				27.1.3
a)	Class B				
i)	3" (75 mm) inner dia.	R.M. R.ft.	145.10 44.25	559.50 170.55	
ii)	4" (100 mm) inner dia.	R.M. R.ft.	145.10 44.25	776.45 236.65	
iii)	5" (125 mm) inner dia.	R.M. R.ft.	217.60 66.35	980.85 298.95	
iv)	6" (150 mm) inner dia.	R.M. R.ft.	217.60 66.35	1,232.10 375.55	
v)	8" (200 mm) inner dia.	R.M. R.ft.	290.15 88.45	1,469.70 447.95	
vi)	10" (250 mm) inner dia.	R.M. R.ft.	290.15 88.45	2,153.00 656.25	
vii)	12" (300 mm) inner dia.	R.M. R.ft.	362.70 110.55	3,003.60 915.50	
viii)	14" (350 mm) inner dia.	R.M. R.ft.	362.70 110.55	3,538.10 1,078.45	
b)	Class D				
i)	1.25" (30 mm) inner dia.	R.M. R.ft.	72.55 22.10	169.60 51.70	
ii)	1.5" (40 mm) inner dia.	R.M. R.ft.	72.55 22.10	196.65 59.95	
iii)	2" (50 mm) inner dia.	R.M. R.ft.	106.40 32.45	291.40 88.80	
iv)	3" (75 mm) inner dia.	R.M. R.ft.	106.40 32.45	487.60 148.60	
v)	4" (100 mm) inner dia.	R.M. R.ft.	145.10 44.25	891.65 271.80	
vi)	6" (150 mm) inner dia.	R.M. R.ft.	145.10 44.25	1,487.00 453.25	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-20	Testing and development of tubewell of size 6" (150 mm) inner dia. and above continuously by pumping raw hiding method.				27.1.6
a)	Upto 1.5 cusecs (0.0425 cumec) discharge	Job	16,279.37	69,127.00	
b)	Above 1.5 cusecs (0.0425 cumec) capacity	Job	16,279.37	81,517.69	
27-21	Shrouding with graded pea gravel 3/8" to 1/8" (10 mm to 3mm) around tubewell bore hole.	Cu.m. Cu.ft.	1,184.80 33.55	2,980.10 84.40	27.1.4
27-22	Providing, laying, cutting, jointing, testing and disinfecting C.I. pipe line in trenches with spigot and socket, chaulked lead or comet joints or flanged joints or tyton joints including cost of materials such as lead, comet and yarn. (Cost of specials and their installation not included).				27.3.1.1
i)	3" (75 mm) inner dia.	R.M. R.ft.	59.50 18.15	2,431.80 741.20	
ii)	4" (100 mm) inner dia.	R.M. R.ft.	59.50 18.15	3,393.95 1,034.50	
iii)	6" (150 mm) inner dia.	R.M. R.ft.	89.20 27.20	5,361.05 1,634.05	
iv)	8" (200 mm) inner dia.	R.M. R.ft.	148.70 45.30	8,056.45 2,455.65	
27-23	Providing, laying, cutting, jointing, testing and disinfecting G.I. pipe line III or equivalent make including the cost of specials and cost of painting 2 coats with bitumen to pipes and specials after cleaning and wrapping tightly hessian cloth soaked in Mexphalt composition around pipes.				27.3.1.1
a)	Light duty				
i)	1/2" (15 mm) inner dia.	R.M. R.ft.	80.30 24.50	277.90 84.70	
ii)	3/4" (20 mm) inner dia.	R.M. R.ft.	80.30 24.50	366.90 111.85	
iii)	1" (25 mm) inner dia.	R.M. R.ft.	92.05 28.05	496.15 151.25	
iv)	1.25" (30 mm) inner dia.	R.M. R.ft.	92.05 28.05	624.35 190.30	
v)	1.5" (40 mm) inner dia.	R.M. R.ft.	108.95 33.20	785.45 239.40	
vi)	2" (50 mm) inner dia.	R.M. R.ft.	108.95 33.20	963.45 293.65	
vii)	2.5" (65 mm) inner dia.	R.M. R.ft.	133.85 40.81	1,303.45 397.39	
viii)	3" (75 mm) inner dia.	R.M. R.ft.	133.85 40.80	1,504.65 458.60	
ix)	4" (100 mm) inner dia.	R.M. R.ft.	148.70 45.30	2,026.85 617.80	
b)	Medium duty				
i)	1/2" (15 mm) inner dia.	R.M. R.ft.	80.30 24.50	343.80 104.80	
ii)	3/4" (20 mm) inner dia.	R.M.	80.30	419.80	




Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
		R.ft.	24.50	127.95	
iii)	1" (25 mm) inner dia.	R.M. R.ft.	92.05 28.05	599.40 182.70	
iv)	1.25" (30 mm) inner dia.	R.M. R.ft.	92.05 28.05	750.20 228.65	
v)	1.5" (40 mm) inner dia.	R.M. R.ft.	108.95 33.20	870.90 265.45	
vi)	2" (50 mm) inner dia.	R.M. R.ft.	108.95 33.20	963.45 293.65	
vii)	2.5" (65 mm) inner dia.	R.M. R.ft.	133.85 40.80	1,495.75 455.90	
viii)	3" (75 mm) inner dia.	R.M. R.ft.	133.85 40.80	1,889.20 575.85	
ix)	4" (100 mm) inner dia.	R.M. R.ft.	148.70 45.30	2,669.55 813.70	
x)	5" (125 mm) inner dia.	R.M. R.ft.	183.30 55.85	3,585.35 1,092.85	
xi)	6" (150 mm) inner dia.	R.M. R.ft.	183.30 55.85	4,200.55 1,280.35	
27-24	Replacing burst/damaged G.I. pipe line with all excavation, cutting, providing new G.I. Heavy duty pipe, union, tees, bends, sockets, including threading etc. and painting with 2 coats of bitumen to pipes and specials after cleaning and wrapping tightly hessian cloth soaked in Maxphalt composition around pipes including cost of testing and disinfecting (cost of pipes and all accessories included) pipe of B.S.S 1387 - 1967.				27.3.1.1 27.3.2
i)	1/2" (15 mm) inner dia.	R.M. R.ft.	92.94 28.35	560.90 170.95	
ii)	3/4" (20 mm) inner dia.	R.M. R.ft.	110.15 33.55	636.90 194.15	
iii)	1" (25 mm) inner dia.	R.M. R.ft.	123.92 37.75	804.75 245.30	
iv)	1.25" (30 mm) inner dia.	R.M. R.ft.	141.62 43.15	955.55 291.25	
v)	1.5" (40 mm) inner dia.	R.M. R.ft.	157.35 47.95	1,059.35 322.90	
vi)	2" (50 mm) inner dia.	R.M. R.ft.	174.94 53.30	1,151.90 351.10	
vii)	2.5" (65 mm) inner dia.	R.M. R.ft.	185.88 56.65	1,659.30 505.75	
viii)	3" (75 mm) inner dia.	R.M. R.ft.	205.10 62.50	2,052.75 625.70	
ix)	4" (100 mm) inner dia.	R.M. R.ft.	220.30 67.15	2,818.25 859.00	
x)	5" (125 mm) inner dia.	R.M. R.ft.	237.92 72.50	3,699.45 1,127.60	
xi)	6" (150 mm) inner dia.	R.M. R.ft.	249.92 76.20	4,314.65 1,315.10	



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
27-25	Providing, laying, cutting, jointing, testing and disinfecting asbestos cement pipe line in trenches including comet joint and rubber ring.				27.3.1.1 27.3.2
a)	Class B working pressure				
i)	3" (75 mm) inner dia.	R.M. R.ft.	145.10 44.25	733.20 223.50	
ii)	4" (100 mm) inner dia.	R.M. R.ft.	145.10 44.25	952.30 290.25	
iii)	6" (150 mm) inner dia.	R.M. R.ft.	217.60 66.35	1,485.20 452.70	
iv)	8" (200 mm) inner dia.	R.M. R.ft.	217.60 66.35	2,307.95 703.45	
v)	10" (250 mm) inner dia.	R.M. R.ft.	362.70 110.55	3,359.45 1,023.95	
vi)	12" (300 mm) inner dia.	R.M. R.ft.	362.70 110.55	4,166.65 1,270.00	
vii)	14" (350 mm) inner dia.	R.M. R.ft.	507.80 154.80	5,387.87 1,642.25	
viii)	16" (400 mm) inner dia	R.M. R.ft.	507.80 154.80	6,713.35 2,046.25	
ix)	18" (450 mm) inner dia.	R.M. R.ft.	652.85 199.00	8,376.70 2,553.25	
x)	20" (500 mm) inner dia.	R.M. R.ft.	652.85 199.00	10,182.00 3,103.50	
xi)	24" (600 mm) inner dia.	R.M. R.ft.	725.40 221.10	13,982.35 4,261.85	
b)	Class C working pressure				
i)	3" (75 mm) inner dia.	R.M. R.ft.	145.10 44.25	701.57 213.85	
ii)	4" (100 mm) inner dia.	R.M. R.ft.	145.10 44.25	963.99 293.85	
iii)	6" (150 mm) inner dia.	R.M. R.ft.	217.60 66.35	1,639.83 499.85	
iv)	8" (200 mm) inner dia.	R.M. R.ft.	217.60 66.35	2,480.98 756.20	
v)	10" (250 mm) inner dia.	R.M. R.ft.	362.70 110.55	3,521.12 1,073.25	
vi)	12" (300 mm) inner dia.	R.M. R.ft.	362.70 110.55	4,769.96 1,453.90	
vii)	14" (350 mm) inner dia.	R.M. R.ft.	507.80 154.80	7,313.17 2,229.10	
viii)	16" (400 mm) inner dia	R.M. R.ft.	507.80 154.80	9,214.54 2,808.65	



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.	
			Labour	Composite		
ix)	18" (450 mm) inner dia.	R.M.	652.85	11,334.78		
		R.ft.	199.00	3,454.90		
x)	20" (500 mm) inner dia.	R.M.	652.85	13,372.05		
		R.ft.	199.00	4,075.85		
xi)	24" (600 mm) inner dia.	R.M.	725.40	18,670.76		
		R.ft.	221.10	5,690.90		
						
c) Class D working pressure						
i)	3" (75 mm) inner dia.	R.M.	145.10	733.20		
		R.ft.	44.25	223.50		
ii)	4" (100 mm) inner dia.	R.M.	145.10	1,129.18		
		R.ft.	44.25	344.20		
iii)	6" (150 mm) inner dia.	R.M.	217.60	2,019.40		
		R.ft.	66.35	615.50		
iv)	8" (200 mm) inner dia.	R.M.	217.60	3,414.63		
		R.ft.	66.35	1,040.80		
v)	10" (250 mm) inner dia.	R.M.	362.70	5,092.93		
		R.ft.	110.55	1,552.35		
vi)	12" (300 mm) inner dia.	R.M.	362.70	7,279.36		
		R.ft.	110.55	2,218.80		
vii)	14" (350 mm) inner dia.	R.M.	507.80	10,840.52		
		R.ft.	154.80	3,304.25		
viii)	16" (400 mm) inner dia.	R.M.	507.80	13,872.32		
		R.ft.	154.80	4,228.35		
ix)	18" (450 mm) inner dia.	R.M.	652.85	16,749.45		
		R.ft.	199.00	5,105.30		
x)	20" (500 mm) inner dia.	R.M.	652.85	20,292.32		
		R.ft.	199.00	6,185.15		
27-26	Providing, laying, cutting, jointing, testing and disinfecting Ductile iron pipe line in trenches including all fittings and accessories.				27.3.1.1	
					27.3.2	
i)	4" (100 mm) inner dia.	R.M.	507.80	1,679.30		
		R.ft.	154.80	511.85		
ii)	6" (150 mm) inner dia.	R.M.	507.80	2,557.95		
		R.ft.	154.80	779.65		
iii)	8" (200 mm) inner dia.	R.M.	652.85	2,995.90		
		R.ft.	199.00	913.15		
iv)	10" (250 mm) inner dia.	R.M.	652.85	3,581.65		
		R.ft.	199.00	1,091.70		
v)	12" (300 mm) inner dia.	R.M.	943.00	5,043.35		
		R.ft.	287.45	1,537.25		
vi)	16" (400 mm) inner dia.	R.M.	943.00	6,214.85		
		R.ft.	287.45	1,894.30		
vii)	18" (450 mm) inner dia.	R.M.	1,450.80	7,308.40		
		R.ft.	442.20	2,227.65		
viii)	20" (500 mm) inner dia.	R.M.	1,450.80	7,894.15		
		R.ft.	442.20	2,406.15		

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
	ix) 24" (600 mm) inner dia.	R.M.	1,740.95	9,355.85	
		R.ft.	530.65	2,851.70	
27-27	Providing and fixing C.I. specials of class-B such as bends, tees, cross, collars, reducers, tail pieces, flanged spigot, caps, flanged sockets, tapers, angle, branch and plugs including turning, threading, facing and fitting for C.I. pipe line.				27.3.1 27.3.2
	a) Cast iron S.S. specials with spigot and socket joint				
	i) 3" to 6" (75 mm to 150 mm) dia.	Kg.	59.50	252.55	
		Lb.	27.00	114.55	
	ii) 8" to 12" (200 mm to 300 mm) inner dia.	Kg.	44.60	248.35	
		Lb.	20.25	112.65	
	iii) 15" to 18" (375 mm to 450 mm) inner dia.	Kg.	29.75	242.95	
		Lb.	13.50	110.20	
	b) Cast iron flanged specials with flanged joints				
	i) 3" to 6" (75 mm to 150 mm) dia.	Kg.	29.75	251.25	
		Lb.	13.50	113.95	
	ii) 8" to 12" (200 mm to 300 mm) inner dia.	Kg.	22.85	247.85	
		Lb.	10.35	112.40	
	iii) 15" to 18" (375 mm to 450 mm) inner dia.	Kg.	14.85	242.30	
		Lb.	6.75	109.90	
	c) Cast iron specials with tyton joints				
	i) 3" to 6" (75 mm to 150 mm) dia.	Kg.	14.85	242.30	
		Lb.	6.75	109.90	
	ii) 8" to 12" (200 mm to 300 mm) inner dia.	Kg.	14.85	244.20	
		Lb.	6.75	110.75	
	iii) 15" to 18" (375 mm to 450 mm) inner dia.	Kg.	14.85	237.75	
		Lb.	6.75	107.85	
27-28	Providing and fixing C.I. special of BSS, Class-B such as bends, tees, cross, collar, reducers, tail pieces, flanged sockets, flanged spigots, caps, tapers, angle branch and plugs for asbestos cement pipe line with comet joint and rubber ring.				27.3.1 27.3.2
	i) 3" to 6" (75 mm to 150 mm) dia.	Kg.	53.11	257.94	
		Lb.	24.10	117.00	
	ii) 8" to 18" (200 mm to 450 mm) inner dia.	Kg.	43.79	250.37	
		Lb.	19.85	113.55	
	iii) 20" to 24" (500 mm to 600 mm) inner dia.	Kg.	37.70	244.97	
		Lb.	17.10	111.10	
27-29	Providing and fixing C.I. sluice valve of BSS quality and weight, Class B, for C.I. pipe line and A.C. pipe line including cost of jointing material.				27.3.1.2
	a) 3" (75 mm) inner dia.	Each	206.74	5,814.67	
	b) 4" (100 mm) inner dia.	Each	206.74	9,036.35	
	c) 6" (150 mm) inner dia.	Each	257.64	14,315.89	
	d) 9" 225 mm inner dia.	Each	257.64	21,159.75	
	e) 12" (300 mm) inner dia.	Each	371.77	43,950.80	
	f) 15" (375 mm) inner dia.	Each	371.77	49,963.29	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
	g) 18" (450 mm) inner dia.	Each	520.47	78,081.61	
	h) 21" (525 mm) inner dia.	Each	520.47	92,163.28	
	i) 24" (600 mm) inner dia.	Each	743.54	114,582.41	
	j) 27" (675 mm) inner dia.	Each	743.54	141,687.85	
	k) 30" (750 mm) inner dia.	Each	892.24	163,761.23	
27-30	Providing and fixing C.I. sluice valve of BSS quality and weight for asbestos cement pipe line with comet joint and rubber ring including cost of jointing material.				27.3.1.2
	a) 3" (75 mm) inner dia.	Each	206.74	5,870.81	
	b) 4" (100 mm) inner dia.	Each	206.74	9,078.71	
	c) 6" (150 mm) inner dia.	Each	257.64	11,945.86	
27-31	Providing and fixing fire hydrants standard pattern 3" (75mm) dia. inlet and 2.5" (65mm) dia screw outlet. BSS quality and weight, cost of jointing material is included.	Each	347.59	3,452.98	27.3.1.4
27-32	Providing and fixing air valve 2.5" (65 mm) inner dia.of BSS quality and weight, cost of jointing material is included.				27.3.2.2
	a) Single	Each	743.54	3,760.20	
	b) Double	Each	743.54	7,641.73	
27-33	Cutting C.I. pipe and welding spigot or socket flanged or tyton end including finishing ends of pipe.				27.3.1.1
	a) 3" to 6" (75 mm to 150 mm) dia.	Per 1" dia. of pipe	33.67	131.33	
	b) 8" to 12" (200 mm to 300 mm) inner dia.	Per 1" dia. of pipe	29.48	120.38	
	c) 15" to 18" (375 mm to 450 mm) inner dia.	Per 1" dia. of pipe	28.38	113.50	
27-34	Providing and installing P.V.C. bends of Shayvl or equivalent make.				27.3.1.1
	a) Class B				
	i) 3" (75 mm) inner dia.	Each	87.05	222.22	
	ii) 4" (100 mm) inner dia.	Each	103.02	464.81	
	iii) 5" (125 mm) inner dia.	Each	115.10	696.20	
	iv) 6" (150 mm) inner dia.	Each	135.41	914.66	
	v) 8" (200 mm) inner dia.	Each	157.65	1,386.43	
	b) Class D				
	i) 1.25" (30 mm) inner dia.	Each	82.21	125.19	
	ii) 1.5" (40 mm) inner dia.	Each	82.21	134.95	
	iii) 2" (50 mm) inner dia.	Each	106.40	185.45	
	iv) 3" (75 mm) inner dia.	Each	106.40	337.75	
	v) 4" (100 mm) inner dia.	Each	145.10	638.55	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.	
			Labour	Composite		
vi)	5" (125 mm) inner dia.	Each	145.10	1,183.90	27.2	
vii)	6" (150 mm) inner dia.	Each	189.55	1,606.15		
27-35	Providing and installing P.V.C. tees of Shayl or equivalent make					
a) Class B						
i)	3" (75 mm) inner dia.	Each	193.45	655.60		
ii)	4" (100 mm) inner dia.	Each	193.45	1,161.00		
iii)	5" (125 mm) inner dia.	Each	270.80	1,643.60		
iv)	6" (150 mm) inner dia.	Each	270.80	2,227.35		
v)	8" (200 mm) inner dia.	Each	304.65	1,894.90		
vi)	10" (250 mm) inner dia.	Each	304.65	3,256.40		
vii)	12" (300 mm) inner dia.	Each	358.85	4,448.20		
viii)	14" (350 mm) inner dia.	Each	358.85	4,374.40		
b) Class D						
i)	1.25" (30 mm) inner dia.	Each	82.21	125.19		
ii)	1.5" (40 mm) inner dia.	Each	82.21	134.95		
iii)	2" (50 mm) inner dia.	Each	106.40	185.45		
iv)	3" (75 mm) inner dia.	Each	106.40	337.75		
v)	4" (100 mm) inner dia.	Each	145.10	638.55		
vi)	5" (125 mm) inner dia.	Each	145.10	1,183.90		
vii)	6" (150 mm) inner dia.	Each	189.55	1,606.15		
27-36	Providing and installing P.V.C. bail or end plug of Shayl or equivalent make.					27.3
a) Class B						27.2
i)	3" (75 mm) inner dia.	Each	19.35	90.40		
ii)	4" (100 mm) inner dia.	Each	19.35	109.70		
iii)	5" (125 mm) inner dia.	Each	27.10	147.35		
iv)	6" (150 mm) inner dia.	Each	27.10	198.80		
v)	8" (200 mm) inner dia.	Each	30.95	360.15		
vi)	10" (250 mm) inner dia.	Each	30.95	484.90		
vii)	12" (300 mm) inner dia.	Each	35.80	606.20		
viii)	14" (350 mm) inner dia.	Each	35.80	671.65		
b) Class D						
i)	1.25" (30 mm) inner dia.	Each	13.55	61.80		
ii)	1.5" (40 mm) inner dia.	Each	13.55	83.25		
iii)	2" (50 mm) inner dia.	Each	14.50	99.05		
iv)	3" (75 mm) inner dia.	Each	14.50	184.65		



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
	v) 4" (100 mm) inner dia.	Each	22.25	228.55	
	vi) 5" (125 mm) inner dia.	Each	22.25	290.75	
	vii) 6" (150 mm) inner dia.	Each	28.05	362.05	
27-37	Providing and installing P.V.C. tapered core of Shayyl or equivalent make.				27.3.1.1
	a) Class B				
	i) 3" (75 mm) inner dia.	Each	83.20	170.15	
	ii) 4" (100 mm) inner dia.	Each	83.20	200.18	
	iii) 5" (125 mm) inner dia.	Each	96.70	243.10	
	iv) 6" (150 mm) inner dia.	Each	96.70	264.25	
	v) 8" (200 mm) inner dia.	Each	118.95	385.22	
	b) Class D				
	i) 1.25" (30 mm) inner dia.	Each	82.20	111.60	
	ii) 1.5" (40 mm) inner dia.	Each	82.20	127.75	
	iii) 2" (50 mm) inner dia.	Each	96.70	142.80	
27-38	Providing and installing P.V.C. conduit of Class B or D of Beta or equivalent make				27.3.1.1
	a) 1.25" (30 mm) inner dia.	Each	82.20	154.20	
	b) 1.5" (40 mm) inner dia.	Each	82.20	181.85	
	c) 2" (50 mm) inner dia.	Each	96.70	235.45	
	d) 3" (75 mm) inner dia.	Each	96.70	313.50	
	e) 4" (100 mm) inner dia.	Each	115.85	462.45	
27-39	Providing and installing P.V.C. V socket of Class B or D of Beta or equivalent make.				27.3.1.1
	a) 1.25" (30 mm) inner dia.	Each	83.20	154.45	
	b) 1.5" (40 mm) inner dia.	Each	83.20	205.25	
	c) 2" (50 mm) inner dia.	Each	96.70	299.15	
	d) 3" (75 mm) inner dia.	Each	96.70	447.65	
	e) 4" (100 mm) inner dia.	Each	117.05	600.85	
27-40	Providing and installing P.V.C. crosser of Beta or equivalent make.				27.3.1.1
	a) Class B				
	i) 3" (75 mm) inner dia.	Each	189.55	376.95	
	ii) 4" (100 mm) inner dia.	Each	189.55	514.80	
	iii) 5" (125 mm) inner dia.	Each	270.80	678.25	
	iv) 6" (150 mm) inner dia.	Each	270.80	869.55	
	v) 8" (200 mm) inner dia.	Each	305.65	1,222.30	
	vi) 10" (250 mm) inner dia.	Each	305.65	1,437.45	

Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
vii)	12" (300 mm) inner dia.	Each	357.85	1,725.35	
viii)	14" (350 mm) inner dia.	Each	357.85	2,117.95	
b)	Class D				
i)	1.25" (30 mm) inner dia.	Each	125.75	223.45	
ii)	1.5" (40 mm) inner dia.	Each	125.75	319.95	
iii)	2" (50 mm) inner dia.	Each	145.10	399.45	
iv)	3" (75 mm) inner dia.	Each	201.23	533.20	
v)	4" (100 mm) inner dia.	Each	221.50	873.20	
vi)	5" (125 mm) inner dia.	Each	221.50	961.95	
vii)	6" (150 mm) inner dia.	Each	305.65	1,153.95	
27-41	Add extra for respective payable item of ground floor				27.6
a)	For first floor	% Increase		0.10	
b)	For every additional floor above first floor	% Increase		0.08	
27-42	Providing, laying, cutting, jointing, testing and disinfecting HDPE pipes density 700-960 kg/cu.m and carbon black contents > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-10, complete in all				27.5
ii)	20 mm	RM Rft	8.03 2.45	49.12 14.97	
iii)	25 mm	RM Rft	8.03 2.45	71.70 21.86	
iv)	32 mm	RM Rft	8.03 2.45	92.45 28.18	
v)	40 mm	RM Rft	8.03 2.45	146.76 44.74	
vi)	50 mm	RM Rft	- -	- -	
vii)	63 mm	RM Rft	8.03 2.45	222.21 67.75	
viii)	75 mm	RM Rft	8.03 2.45	349.99 106.70	
ix)	90 mm	RM Rft	8.03 2.45	489.94 149.37	
x)	110 mm	RM Rft	8.03 2.45	698.04 212.82	
xi)	125 mm	RM Rft	10.11 3.08	1,033.56 315.11	
xii)	160 mm	RM Rft	10.11 3.08	1,313.10 400.34	
xiii)	180 mm	RM Rft	10.11 3.08	1,743.04 531.42	





Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
xiv)	200 mm	RM	10.11	2,161.67	27.5
		Rft	3.08	659.05	
xv)	225 mm	RM	10.11	2,733.64	
		Rft	3.08	833.43	
xvi)	250 mm	RM	10.11	3,368.89	
		Rft	3.08	1,027.10	
xvii)	280 mm	RM	11.15	6,011.43	
		Rft	3.40	1,832.75	
xviii)	315 mm	RM	11.15	6,918.56	
		Rft	3.40	2,109.32	
xix)	350 mm	RM	-	-	
		Rft	-	-	
xx)	400 mm	RM	-	-	
		Rft	-	-	
27-43	Providing, laying, cutting, jointing, testing and disinfecting HDPE pipes density 700-960 kg/cu.m and carbon black contents > 2% with DIN-8074, 8075 or PS-3580:1997 (rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-16, complete in all respects with specials and valves etc.				
i)	(20mm)	RM	8.03	61.09	
		Rft	2.45	18.63	
ii)	(25mm)	RM	8.03	93.65	
		Rft	2.45	28.55	
iii)	(32mm)	RM	8.03	131.04	
		Rft	2.45	39.95	
iv)	(40mm)	RM	8.03	211.26	
		Rft	2.45	64.41	
v)	50mm)	RM	-	-	
		Rft	-	-	
vi)	(50mm)	RM	8.03	324.43	
		Rft	2.45	98.91	
vii)	(63mm)	RM	8.03	505.76	
		Rft	2.45	154.20	
viii)	(75mm)	RM	8.03	710.21	
		Rft	2.45	216.53	
ix)	(90mm)	RM	8.03	1,015.66	
		Rft	2.45	309.65	
x)	(110mm)	RM	10.11	1,504.52	
		Rft	3.08	458.70	
xi)	(125mm)	RM	10.11	1,948.71	
		Rft	3.08	594.12	
xii)	(160mm)	RM	10.11	2,896.71	
		Rft	3.08	883.14	
xiii)	(180mm)	RM	10.11	4,014.91	
		Rft	3.08	1,224.06	
xiv)	(200mm)	RM	11.15	4,960.48	
		Rft	3.40	1,512.34	



Sr. No.	Description	Unit	Rate (Rs.)		Ref. Tech. Specs.
			Labour	Composite	
xv)	(225mm)	RM Rft	11.15 3.40	6,271.14 1,911.93	27.6
xvi)	(250mm)	RM Rft	11.15 3.40	7,713.22 2,351.59	
xvii)	(280mm)	RM Rft	11.15 3.40	8,945.82 2,727.38	
xviii)	(315mm)	RM Rft	12.19 3.72	10,019.17 3,054.62	
xix)	(350mm)	RM Rft	12.19 3.72	11,220.30 3,420.82	
xx)	(400mm)	RM Rft	12.19 3.72	12,565.03 3,830.80	
27-44	Providing and fixing LDPE overhead tank manufactured by Dura or equivalent on top of any floor				
i)	300 gallons capacity	Each	1,709.05	19,654.00	
ii)	500 gallons capacity	Each	1,033.70	28,819.40	
iii)	1000 gallons capacity	Each	1,033.70	59,885.40	
iv)	1200 gallons capacity	Each	1,033.70	70,015.60	
27-45	Cleaning of overhead water tank	Cu.m. Cu.ft.	17.00 0.50	17.50 0.50	
27-46	Supply and fixing 1/8" thick galvanized iron sheet water tank of approved design and size including covering and locking arrangement	Each	1,033.70	51,267.80	

